

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford

County, Sec. 4 Twp. 22S Rge. (E) 12(W)

Location as "NE/CNW%SW%" or footage from lines SW SW NE

Lease Owner Leben Drilling, Inc.

Lease Name Stargel Well No. 1

Office Address 905 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 4, 19 56

Application for plugging filed September 4, 19 56

Application for plugging approved September 4, 19 56

Plugging commenced September 4, 19 56

Plugging completed September 4, 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3654 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 277'   |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Rotary mud w/1/3 sk hulls to 240' - Plug w/ 20 sks. cement poured through drill pipe - Mud w/1/3 sks to 35' and Plug w/10 sks. cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address 905 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

James M. Battin (employee of owner) of ~~(owner)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Battin

905 Central Building, Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of September, 19 56

My commission expires July 10, 1957

John Thomas Notary Public.

PLUGGING  
FILE SEC. 4 T. 22 R. 12W  
BOOK PAGE 96 LINE 38

REC. 9-13-56

CONTRACTOR'S WELL LOG

Leben Drilling, Inc.  
 Stargel #1  
 SW SW NE of Sec. 4-22S-12W  
 Stafford County, Kansas

|      |      |                                      |
|------|------|--------------------------------------|
| 0    | 163  | Surface Clay and Sand                |
| 163  | 277  | Sand and Shale                       |
| 277  | 400  | Shale, Shells and Sand               |
| 400  | 520  | Red Bed                              |
| 520  | 656  | Shale and Red Bed                    |
| 656  | 682  | Anhydrite                            |
| 682  | 795  | Shale and Shells                     |
| 795  | 977  | Shale and Red Bed                    |
| 977  | 1252 | Shale and Shells                     |
| 1252 | 1461 | Shale and Lime                       |
| 1461 | 1561 | Lime and Shale                       |
| 1561 | 1682 | Shale and Lime                       |
| 1682 | 1755 | Lime and Shale                       |
| 1755 | 1889 | Lime and Shale                       |
| 1889 | 1912 | Sandy Lime                           |
| 1912 | 1986 | Shale and Lime                       |
| 1986 | 2047 | Lime and Shale                       |
| 2047 | 2146 | Shale and Lime                       |
| 2146 | 2324 | Lime and Shale                       |
| 2324 | 2518 | Shale and Lime                       |
| 2518 | 2653 | Shale                                |
| 2653 | 2889 | Shale and Lime                       |
| 2889 | 2982 | Lime and Shale                       |
| 2982 | 3102 | Shale and Lime                       |
| 3102 | 3182 | Lime                                 |
| 3182 | 3293 | Shale                                |
| 3293 | 3509 | Lime                                 |
| 3509 | 3569 | Lime and Shale                       |
| 3569 | 3589 | Cherty Lime                          |
| 3589 | 3645 | Shale and Lime                       |
| 3645 | 3646 | Lime and Shale                       |
| 3646 | 3649 | Arbuckle                             |
| 3649 | 3654 | Lime                                 |
|      | 3654 | <u>Rotary Total Depth, D &amp; A</u> |

COMMENCED: August 23, 1956

COMPLETED: September 4,  
1956

## SURFACE CASINGS:

Set 8 5/8" at 277'  
 w/225 sacks cement  
 2% Ca. Cl.

State of Kansas )  
 County of Sedgwick ) ss:

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Stargel #1 SW SW NE of Section 4-22S-12W, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc..

*James M. Battin*

Subscribed and Sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 6th day of September, 1956.

*John Thomas*  
 (Notary Public)

My commission expires July 10, 1957.

|          |         |       |        |
|----------|---------|-------|--------|
| PLUGGING |         |       |        |
| FILE     | SEC. 4  | T. 22 | R. 12W |
| BOOK     | PAGE 96 | LINE  | 38     |