


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD *SE NW SE*



Locate well correctly on above Section Plat

Stafford County, Sec 4 Twp 22 Rge 12 (E) (W) X
Location as "NE/CNW/SW" or footage from lines *SE NE/4 NW/4 SE/4*
Lease Owner H. A. Chapman
Lease Name Schrader Well No. #2
Office Address Box 65 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 6-10-74 _____ 19____
Plugging completed _____ 6-12-74 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3671' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3553'	1401.29'
				8 5/8"	321.19'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 1700'. Mixed and ran 5 sacks cement thru dump bailer.
Plugged hole with 3 sacks hulls - 20 sacks gel and 100 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 12 day of June, 1974
My commission expires 24 October 1976

Sidney D. Miller
Notary Public.



STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- SCHRAEDER #2
Located: NE NW SE, Section 4-22S-12W, Stafford County, Kansas

OWNER: H. A. Chapman Investments
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 7, 1973
COMPLETED: November 15, 1973

TOTAL DEPTH: 3671'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 333 Clay, Sand and Red Bed	Ran 8 joints 8 5/8" 20# Foster pipe,
333 - 665 Shale	321.19' cemented with 250 sacks 3% 50/50 Pozmix, 2% gel. Plug down at 4:50 PM, 11-7-73.
665 - 690 Anhydrite	
690 - 910 Shale	
910 - 1715 Shale and Shells	
1715 - 2020 Shale and Lime	
2020 - 2185 Lime	
2185 - 2734 Lime and Shale	
2734 - 2773 Lime	
2773 - 3115 Lime and Shale	
3115 - 3415 Lime	
3415 - 3470 Lime and Shale	
3470 - 3560 Lime	
3560 - 3655 Lime and Shale	
3655 - 3671 Lime	Ran 115 joints 5 1/2" 11# 8rd casing. Cemented at 3553'. Stage 1 - 125 sacks Pozmix with 2% gel and 18% salt saturated. Stage 2 - 150 Sacks Halco Light. Plug down at 5:30 AM, 11-13-73.

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1974
CONSERVATION DIVISION
Wichita, Kansas