

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,710-0000

LEASE NAME Stargel

TYPE OR PRINT

WELL NUMBER #1

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2970 Ft. from S Section Line

1650 Ft. from E Section Line

LEASE OPERATOR Pintail Petroleum Ltd.

SEC# TWP.22 RGE. 12 (E) or (W)

ADDRESS 412 E. Douglas, Suite One, Wichita, Ks. 67202

COUNTY Stafford

PHONE# (316) 687-3450 OPERATORS LICENSE NO. 5086

Date Well Completed _____

Character of Well Oil

Plugging Commenced 9-11-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-23-90

The plugging proposal was approved on September 12, 1990 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	314'	None
				5-1/2"	3745'	2506.58'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand 3300' and 5 sacks cement. Shot casing at 2931', 2764', 2641' and 2500'. Pulled 64 joints of 5-1/2" casing. Howco plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls and 125 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 550 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum, Inc. 10-26-90

STATE OF Kansas COUNTY OF Barton, ss. OCT 26 1990

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1990

My Commission Expires:

