

RECEIVED  
CONSERVATION DIVISION  
STATE CORPORATION COMMISSION


DEC 18 1980

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Wichita, Kansas Twp. 22S Rge. 12W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines \_\_\_\_\_  
NW NE SW  
Lease Owner Kelso Casing Pulling  
Lease Name Sittner #2 Well No. \_\_\_\_\_  
Office Address Box 176, Chase, Kansas 67524  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 11/24/80 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 12/3/80 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3639'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286	None
				2-1/2"	3638	2425'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved onto location. Checked hole to 2850. Cut off head. Pulled 28 1/2" tension. Made shots at 2825, 2610, 2515 and 2425. Pulled total of 80 joints. Squeezed bottom with 10 sacks cement. Plugged well with 4 sacks hulls, 20 sacks gel, 1 sack hulls, plug, and 100 sacks cement. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 80

My commission expires \_\_\_\_\_



[Signature]  
Notary Public.

DRILLERS LOG

TO: WESTERN PETROLEUM Co., INC.    LOCATION:    NW NE SW, SEC. 4-22S-12W  
 STAFFORD COUNTY, KANSAS  
FROM: WESTERN PETROLEUM Co., INC.    ELEVATION:    1867 KB  
NAME:    SITTNER    CASING USED:    8-5/8" AT 286' W/250 SX  
 POZMIX / 3 SX C.C. / 3 SX  
 A.C.  
DATE:    JUNE 12, 1961    5-1/2" AT 3638' W/100 SX 50-50  
 POZMIX, 2% JELQ  
DATE:    JUNE 21, 1961

CLAY AND SAND	80
SAND	95
SHALE AND SAND	195
SHALE	287
RED BED	663
ANHYDRITE	684
SHALE AND SHELLS	1150
SHALE AND LIME	1530
LIME W/SHALE STREAKS	1695
LIME AND SHALE	2072
SHALE AND LIME	2841
LIME AND SHALE	3294
LIME	3470
LIME AND SHALE	3542
VIOLA	3567
CHERT AND SHALE	3605
ARBUCKLE	3639
ROTARY TOTAL DEPTH	3639

RECEIVED  
 STAFFORD COUNTY, KANSAS  
 JUN 21 1961