

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.185.19396-0000

LEASE NAME Sittner

WELL NUMBER A-2

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 4 TWP. 22S RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed 12-22-61

Plugging Commenced 6-25-90

Plugging Completed 7-18-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Parrish Corporation

ADDRESS P.O. Box 221 Great Bend, KS. 67530

PHONE# (316) 792-2621 OPERATORS LICENSE NO. 5228

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3862'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8'	265'	none
				5 1/2'	3710'	2682'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Sanded bottom to 3650' rans 5 sacks cement. Shot pipe @3000', 2800', Mixed 33# hulls, 2 sacks gel, hole in surface

Run tubing to 960' pumped 60 lbs. hulls and six sacks gel Pulled to 720' pumped 50 sks. 60/40 6% gel & two sacks of cc. Pulled tubing out and let set runback

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Parrish Corporation

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) COOPER (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 26 day of July, 19 90

*Jane Herzberg*  
Notary Public

My Commission Expires:         



STATE OF KANSAS  
STATE CORPORATION COMMISSION-CONSERVATION DIVISION  
500 Insurance Building-212 North Market  
Wichita 2, Kansas

DATA AND AFFIDAVIT

(File one Copy)

(On Cementing in Surface or Drive Pipe and required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137, and 55-138, 1947 Supplement to G. S. Kansas 1935)

Lease Owner WESTERN PETROLEUM Co., Inc.Office Address 925 PATTON ROAD, GREAT BEND, KANSASLease Name SITTNER "A" Well No. #2Well Location (Example: C N/2 NE/4 NE/4 or footage from lines)  
NE SW NW SEC 4 TWP 22 RGE 12 (E) County STAFFORDContractor WESTERN PETROLEUM Co., Inc.Office Address 925 PATTON ROAD, GREAT BEND, KANSASDrilled with (~~XXXXXX~~) (Rotary) tools: Date pipe set 12/4 1961SURFACE HOLE DATASURFACE PIPE DATASize of Hole 12 1/4" Csg. (New) (~~XXXXXX~~) Size 8-5/8" Wt. 20#Depth 265' Where set 265'METHOD OF CEMENTING

(a) Cement: Amount and kind 260 SXS OF COMMON CEMENT, 2% JELL, 3 SXS-CACL  
Method: (By Service Co., Dump, Tog., etc.) & 3 SXS A. C. GLOBE CEMENT Co.  
Est. Height Cement behind pipe CIRCULATED

(b) Cementing Material: Explain method. (Example: 8-5/8 w/swag nipple run inside 15", Bridge hold 2/rock and hole filled with cementing material, 15" pipe pulled.)

Describe cementing material COMMON CEMENT, JELL, CACL, A.C.GROUND WATER INFORMATIONDepth to bottom of lowest fresh water producing stratum 100'Name of lowest fresh water producing stratum SURFACESurface elevation of well 1868 K.B.ADDITIONAL INFORMATION

(Additional Information may be submitted on separate sheet)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON SS,  
E. L. COPELAND, of the WESTERN PETROLEUM Company, being  
first duly sworn on oath, state: That I have knowledge of the facts,  
statements and matters herein contained and that the same are true  
and correct.

Subscribed and sworn to before me on this 5TH day of DECEMBER 1961.  
My Commission Expires:

JUN 27, 1965

Janice M. Becker  
JANICE M. BECKER, NOTARY PUBLIC

DRILLERS LOG

SITTNER "A" #2

CASING RECORD: 7 JTS 8-5/8" 20# PIPE.  
 COMPANY: WESTERN PETROLEUM CO., INC.  
 DESCRIPTION: NE SW NW SECTION 4-T225-R12W STAFFORD COUNTY, KANSAS  
 125 JTS 5 1/2" 14# CASING.  
 CONTRACTOR: WESTERN PETROLEUM CO., INC.  
 COMMENCED: DECEMBER 4, 1961  
 ELEVATION: 1865 DF 1868 KB  
 COMPLETED: DECEMBER 15, 1961  
 TOTAL DEPTH: 3860' RTD

FORMATION:	FROM	TO	REMARKS
SAND CLAY	0	40	SPUD @ 2:30 PM 12/4/61. RAN 7 JTS 8-5/8" 20# NEW PIPE (261.22'). SET @ 265' W/ 260 SXS OF COMMON CEMENT, 2# JELL, 3 SXS CACL AND 3 SXS A.C. PLUG DOWN 7:45 PM 12/4/61.
SAND GRAVEL	40	210	
SHALE	210	268	
RED SD	268	662	
ANHYDRITE	662	850	
SHALE AND SHELLS	850	1540	
SHALE AND LIME	1540	1740	
LIME AND SHALE	1740	2290	
SHALE AND LIME	2290	2565	
LIME AND SHALE	2565	3043	
LIME	3043	3145	DST #1 3425-45'. Op. 57". WEAK BLW 17" REC. 62' ROTARY MUD, FEW OIL SPECKS. ICHP 1000#/30", FBHP 480#/30" IFF - FFP 0/
LIME AND SHALE	3145	3310	
LIME	3310	3510	DST #2 3485-3510'. Op. 51". WEAK BLW 26". REC. 65' ROTARY MUD W/ FEW OIL SPECKS. ICHP 510#/30", FBHP 0#/30" IFF - FFP 0/
LIME AND CHERT	3510	3565	
CHERT LIME	3565	3606	SET 125 JTS 5 1/2" 14# CASING @ 3710' W/ 100 SXS 60-40 POZNIX (SALT SATURATED) PLUG DOWN 2:35 PM 12/15/61.
LIME AND SHALE	3606	3765	
CHERTY LIME AND SHALE	3765	3840	
LIME	3840	3860	
RTD	3860		
ANHYDRITE	665	-1203	
NEEDLER	3154	-1286	
JATAN	3290	-1422	
LANING	3304	-1436	
B/XC	3522	-1694	
CONGLOMERATE	3540	-1680	
VIOLA	3562	-1694	
SIMPSON	3602	-1734	
ARBUCKLE	3670	-1802	

STATE OF KANSAS }  
 COUNTY OF BARTON } ss

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

*John H. Volosin*  
 JOHN H. VOLOSIN, GENERAL MANAGER

SUBSCRIBED AND SWORN TO BEFORE ME THIS 18TH DAY OF DECEMBER, 1961

*Janice M. Becker*  
 JANICE M. BECKER, NOTARY PUBLIC

*June 27, 1965*