

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Stafford County. Sec. 31 Twp. 22S Rge. 11W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE NW NE
Clinton Oil Company

Lease Owner. Heyen B#2 Well No.

Office Address. Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Oil - conv. to inj 10/72

Date well completed Dec 1935

Application for plugging filed Nov 30 1972

Application for plugging approved Dec 1 1972

Plugging commenced 2/5/73 19

Plugging completed 2/19/73 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production Inj well 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein

Producing formation L/KC Depth to top 3386 Bottom 3418 Total Depth of Well 3549 Feet

Show depth and thickness of all water, oil and gas formations. (injection perfs)

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil	3529	3549	13"	193	none
L/KC	Oil	3386	3418	7"	3529	1784

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3525', pushed plug to 3375' and ran sand and 6 sacks of cement. Pipe was loose, pulled 57 joints. Bailed hole and set rock bridge, ran 7 yards concrete.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.

Name of Plugging Contractor CHASE, KANSAS
Address

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

(Address) 73

SUBSCRIBED AND SWORN TO before me this 20th day of February, 1973

My commission expires



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Notary Public.

FORMATION RECORD

Give detailed description and thickness of all formations drilled through and contents of sands, whether dry, water, oil or gas.

Formation	Top	Bottom	Formation	Top	Bottom
Surface	0	15			
Sand	15	135			
Red bed	135	165			
Sand	165	175			
Red Bed	175	535			
Anhydrite	535	551			
Red Bed	551	600			
Shale & shells	600	1030			
Salt	1030	1290			
Shale & shells	1290	1430			
Shale	1430	1440			
Lime	1440	1610			
Shale	1610	1638			
Shale & lime	1638	1890			
Broken lime & shale	1890	1997			
Lime	1997	2027			
Broken lime & shale	2027	2100			
Broken lime	2100	2168			
Lime	2168	2198			
Shale	2198	2333			
Broken lime	2333	2416			
Sandy shale	2416	2446			
Broken lime	2446	2637			
Lime	2637	2675			
Broken lime	2675	2978			
Shale	2978	3000			
Broken lime	3000	3037			
Lime	3037	3095			
Broken lime	3095	3221			
Shale	3221	3230			
<u>CORING RECORD</u>					
Dark shale	3230	3235			
Lime - little shale	3235	3239			
Lime	3239	3250			
Broken lime	3250	3305			
Lime	3305	3519			
Gray, green & red shale	3519	3524			
Sandy shale - green	3524	3529			
Dolomite - Small show Oil	3529	3535			
Lime and shale	3535	3549			
		3549 T.D.			

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1972
CONSERVATION DIVISION
Wichita, Kansas