

**AFFIDAVIT OF COMPLETION FORM**

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Parrish Corporation

API NO. 15-185-21,384-0000

ADDRESS 110 North Market Suite 201  
Wichita, Kansas 67202

COUNTY Stafford

FIELD German Valley

\*\*CONTACT PERSON Lloyd Parrish  
PHONE (316) 263-8726

PROD. FORMATION Arbuckle

LEASE Sittner

PURCHASER Western Curde Gathering

WELL NO. 1

ADDRESS P. O. Box 5568  
Denver, Colorado 80217

WELL LOCATION SW-NE-SW

990 Ft. from South Line and

990 Ft. from West Line of

the 4 SEC 22S TWP 12 RGE. W

4-22-12W

DRILLING H-30, Inc.

CONTRACTOR


ADDRESS 251 North Water Suite 10

Wichita, Kansas 67202

PLUGGING

CONTRACTOR

ADDRESS



WELL PLAT

KCC

KGS

MISC

(Office Use)

TOTAL DEPTH 3645 PBTD ----

SPUD DATE 8-25-81 DATE COMPLETED 9-4-81

ELEV: GR 1863 DF 1865 KB 1868

DRILLED WITH (~~CABLE~~) (~~ROTARY~~) (~~AIR~~) TOOLS

(New) / (~~Used~~) casing.

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28	296	50/50 Poz	225	2% Gel - 3% CaCl
Production	7 7/8	4 1/2	10.5	3639	50/50 Poz	175	2% Gel - 18% NaCl

**LINER RECORD**

Top, ft.	Bottom, ft.	Sacks cement

**PERFORATION RECORD**

Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used
None

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1981

CONSERVATION DIVISION  
Wichita, Kansas

CO-1 Filed 10-10-81

11-10-81

Date of first production <u>10-10-81</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pump</u>	Gravity <u>40</u>
---	--	----------------------

RATE OF PRODUCTION PER 24 HOURS	Oil <u>15</u> bbls.	Gas <u>----</u> MCF	Water <u>92</u> %	Gas-oil ratio <u>175</u> bbls.	CFFB
---------------------------------	------------------------	------------------------	----------------------	-----------------------------------	------

Disposition of gas (vented, used on lease or sold): Perforations open hole 3641-3645

\*\*The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

WICHITA, KANSAS  
NOV 23 1981

Name of lowest fresh water producing stratum Quat. Depth 193

Estimated height of cement behind Surface Pipe Surface

DV USED? \_\_\_\_\_

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth	
4-22-12W SW NE SW STAFFORD API 15-185-21,384 ELV 1868 KB/LOG HEEB 3143-1275 *TOR 3161-1293 DOUG 3179-1311 BR LM 3280-1412 LANS 3296-1428 BKC 3523-1655 VIOLA 3531-1663 SIMP SH 3583-1755 ARB 3640-1772 RTD 3639-1771 LTD 3645-1777 *SAMPLE TOP MICT - CO, SWB DWN, SHOWING OIL @ 3000' 890' WTR, SWB DWN, REC 56.84 BF, SWB AVG 13 BFPH, 38% OIL RAN LOG, SWB DWN, REC 53.90 BF, 20% OIL, SWB 8.36 BF, 41% OIL/30", R&T, POP, P 15 BOPD + 175 BWPD 10/10/81 P 15 BO & 175 BWP, ARB OH 3336-3345			PARRISH OIL CO. #1 SITTNER 110 N. HARKEY, #201, WICHITA, KS CONTR: H-30, INC; PTD 3700 3 3/4 N & 1 E OF HUDSON, KS FLD: GERMAN VALLEY FR 8/12/81; SPD 8/25/81 8-5/8" 296/275sx, 4 1/2" 3336/125sx DST (1) 3300-3340/30-45-60-45, 1720' GIP, REC 180' VSD&GCM, SIP 969-977#, FP 46-51/76-92# DST (2) 3405-3426/30-60-60-90, GTS (2ND OP) GA 3370 CFG/1ST DAY, 1680 CFG/2ND DAY, REC 90' GCM, SIP 376-346#, FP 30-38/46-53# DST (3) 3430-3445/30-60-60-90, GTS 28", REC 150' GVMO, 300' OCMW, SIP 1002-949#, FP 88-128/160-246# DST (4) 3448-3465/30-60-60-90, GTS, REC 170' GVMO, 30' O&GCM, SIP 856- 818#, FP 38-53/69-92#, BHT 110' DST (5) 3470-3485(LANS K)/30-60-60-90 800' GIP, 55' HO & GCM, SIP 330- 330#, HP 23-30/30-30#, BHT 110' DST (6) 3636-3639(ARB)/30-60-60-90, GTS/45", REC 450' GO, 120' GMO, SIP 1205-1212#, FP 36-76/100-200# BHT 115'		

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS,

Lloyd K. Parrish Jr. OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (FOR) (OF) Parrish Corporation

OPERATOR OF THE Sittner LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 24th DAY OF September, 1981, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Lloyd K. Parrish Jr.

SUBSCRIBED AND SWORN BEFORE ME THIS 17th DAY OF November 1981

Deborah R. Haddock  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: April 24, 1985

