

1 080545

146 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,298-0000
SE SE NE, SEC. 16, T 22 S, R 12 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6566a Oil Corporation

Lease Name Willinger T Well # 2

Operator: Leben Oil Corporation
Name & Address: P.O. Box 21468
Tulsa, OK 74121-1468

County Stafford 120.58

Well Total Depth 3710 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kaiser-Francis Oil Company License Number 6568

Address P.O. Box 35528 Tulsa, OK 74135

Company to plug at: Hour: 12:30 p.m. Day: 22 Month: 8 Year: 1986

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Comp. (phone) 918-494-0000

were: 5 1/2 at 3705' PBTD 3525' Perf at 3501' Anhydrite 675'

1st plug sand back to 3450 and dump 5 sx cement on top of sand through bailer
2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hull,
120 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 22 Month: 8 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3450' and dumped 5 sx cement on top of
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sx hull, 120 sx cement.

Maximum pressure 500 psi and shut in 350 psi.

Remarks: Recovered 1670' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1986

8-27-86

Signed _____
(TECHNICIAN)

INV. NO. 14830

AUG 27

8-22