


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 16 Twp. 22S Rge. 12W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE/4 SW/4 NE/4  
Lease Owner Birmingham-Bartlett Drilling Co., et al  
Lease Name Schade Well No. 3  
Office Address 300 Kaufman Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 19 19 53  
Application for plugging filed (Verbal) March 19 19 53  
Application for plugging approved (Verbal) March 19 19 53  
Plugging commenced March 19 19 53  
Plugging completed March 19 19 53  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Arbuckle test Depth to top 3681' Bottom  Total Depth of Well 3690 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO   | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
|           |         | 0    | 225' | 8-5/8" | 225'   | None       |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from  feet to  feet for each plug set.

Plugged hole. Set bottom plug at 215' with 1/2 sack hulls and 20 sacks cement. Top plug at 35' with 10 sacks cement.

3-29-53  
RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Birmingham-Bartlett Drilling Co.  
Address 300 Kaufman Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick  
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., owner and operator,  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard Hindery  
300 Kaufman Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 19 53

Beverly Larson  
Notary Public.

My commission expires October 2, 1954.

PLUGGING  
FILE SEC 16 T 22 S 12 W  
BOOK PAGE 85 LINE 10

SCHADE NO. 3 WELL

LOCATION: SE/4 SW/4 NE/4  
Section 16-22S-12W  
Stafford County, Kansas

SPUDED: 3- 8-53  
COMPLETED: 3-19-53

OPERATOR and  
CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 8-5/8" casing cemented at 225'  
with 225 sacks and 2 cc.

OIL STRING: None set. Dry and Abandoned.

LOG

(Figures indicate bottom of formation)

|     |      |                  |
|-----|------|------------------|
| 0 - | 145  | Sand             |
|     | 225  | Shale            |
|     | 240  | Shale and shells |
|     | 660  | Red bed          |
|     | 690  | Anhydrite        |
|     | 1575 | Shale and shells |
|     | 2290 | Broken lime      |
|     | 2860 | Shale and shells |
|     | 3580 | Lime             |
|     | 3625 | Chert            |
|     | 3650 | Lime             |
|     | 3681 | Shale            |
|     | 3690 | Arbuckle         |
|     | 3690 | RTD - D & A      |

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Schade No. 3 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me  
this 20th day of March 1953.

Beverly Larson  
Notary Public

My commission expires

October 2, 1954

PLUGGING  
FILE SEC 16 T 22 R 12W  
BOOK PAGE 85 LINE 40