

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
220 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-20,280-0000

LEASE NAME WILLINGER T

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Leben Oil Corporation

SEC. 16 TWP. 22S RGE. 12 XX or (W)

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

COUNTY Stafford

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6566

Date Well Completed 8-11-70

Character of Well Oil

Plugging Commenced 8-22-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-22-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1, Dodge City, KS

Is ACO-1 filed? on old form If not, is well log attached? ---

Producing Formation LKC, Viola, Depth to Top 3308 Bottom 3673 T.D. 3673  
Simpson, Arbuckle O.A.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Viola	Oil	3565	93	8-5/8	288	-0-
Simpson	Oil	3617	20	5-1/2	3672	1520
Arbuckle	Oil	3672	73			
LKC	Oil	3308	3498			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Set bottom hole rubber plug @ 3280'. Filled w/sand + 5 SXS cement to 3230'.  
Shot 5-1/2" casing & POOH 1520'. Pumped 170 SXS cement, 3 SXS hulls, 25 gel  
from approximately 1700' to SURF.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa OK

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 86

Carol Sue Brungardt  
Notary Public

My Commission Expires: 2/11/89

9-12-86

SEP 12

# WELL LOG

Company Al Tipton  
 Contractor Leben Drilling, Inc.  
 Farm Willinger #1  
 Total Depth 3672½'  
 Commenced 8-3-70  
 Completed 8-11-70


Sec. 16 T. 22S R. 12W  
 Loc. NE SE NE  
 County Stafford  
 Casing 8 5/8" 20# New casing set @ 288'  
 w/225 sxs. Common 2% C.C.  
 Production  
 Producer


### Figures Indicate Bottom of Formations

165	Sand & Shale
180	Shale & Sand
288	Red Bed
650	Shale, Red Bed
668	Anhydrite
1030	Red Bed & shale
1425	Shale
3280	Lime & Shale
3672½	Lime
<u>3672½</u>	<u>RTD</u>

State of Kansas  
 County of Barton  
 SS

I, James R. Rodgers of Leben Drilling, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Willinger #1



STATE CONSERVATION COMMISSION  
 JUN 16 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas

James R. Rodgers

Subscribed and sworn to before me this 15th day of August, 1970

My Commission Expires:  
 November 13, 1973

Helen L. Lindenmuth