


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec.16 Twp.22S Rge.12W (E)(W)  
Location as "NE/CNW/SW" or footage from lines BX NW SW NW  
Lease Owner Howard Alexander  
Lease Name Brensing Well No.1  
Office Address P. O. Box 1043, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9-15-66 19  
Application for plugging filed 9-15-66 19  
Application for plugging approved 9-15-66 19  
Plugging commenced 9-15-66 19  
Plugging completed 9-15-66 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Herman Justice, Nickerson, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3712 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	231'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 200', 1/4 sk. hulls, Plug, 25 sks. cement through drill pipe  
Mudded to 40', 1/4 sk. hulls, Plug, 10 sks. cement  
Put 2 sacks cement in rathole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 21 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1966

My commission expires April 1, 1967 Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Howard Alexander  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: BRENSING #1  
 LOCATION: NW SW NW SEC. 16-22S+12W  
 STAFFORD COUNTY, KANSAS  
 COMMENCED: 9-5-66  
 COMPLETED: 9-15-66

0	45	Clay, Sand
45	195	Sand
195	665	Shale
665	686	Anhydrite
686	966	Shale
966	1550	Shale, Shells
1550	1610	Lime, Shale
1610	2070	Lime
2070	2350	Shale, Lime
2350	2780	Shale
2780	2950	Shale, Lime
2950	3175	Lime
3175	3265	Lime, Shale
3265	3600	Lime
3600	3641	Viola
3641	3675	Simpson
3675	3699	Arbuckle Lime, Shale
3699	3712	Arbuckle Lime
	<u>3712</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 21 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" used surface casing @ 231' cemented with 200 sacks  
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is  
 a true and correct copy of the log of the Brensing #1 Well, located  
 NW SW NW of Section 16, Township 22 South, Range 12 West, Stafford  
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in  
 and for Barton County, Kansas, this 20th day of September, 1966.

*Ulanda Nichols*

Ulanda Nichols

My Commission Expires:  
 April 1, 1967