

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,922-0000

LEASE NAME Spangenberg

WELL NUMBER #2

1980 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 16 TWP. 22 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 6-19-90

Plugging Completed 6-29-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Woodman-Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Ks. 67530

PHONE# (316-792-1934) OPERATORS LICENSE NO. 6588

Character of Well Dual SWD-Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 29, 1990 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3927'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	297'	None
				5-1/2"	3840'	2,539.96'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3800' and 5 sacks of cement. Pushed plug to 3350' and dumped 5 sacks cement. Shot casing at 2911', 2740' & 2532'. Pulled 64 joints of 5-1/2" casing. B.J. Services plugged well with 350# hull, 10 sacks gel, 50 sacks cement, 10 sacks gel, 50# hulls, released plug and pumped 125 sacks 60/40. pozmix cement with 6% gel. Max pressure was 500 psi and shutin 250 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530 7-2-90

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Co. JUL - 2 1990

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO before me this 29th day of June, 1990

My Commission Expires _____



Iona M. Leatherman
Notary Public