

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15485-22076-0000
API NUMBER Docket # D-23,758
LEASE NAME Mawhirter SWD
WELL NUMBER 3
3300 Ft. from (S)N Line of Section (circle one)
4950 Ft. from (W)W Line of Section (circle one)

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE OPERATOR Pratt Well Service Inc.
ADDRESS PO Box 847
CITY, STATE, ZIP Pratt, ks. 67124
PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893
Character of Well SWD
(Oil, Gas, D&A, (S)W, Input, Water Supply Well)

SPOT LOCATION C - SW - NW
SEC. 2 TWP. 23S S. RGE 13
COUNTY Stafford
Date Well Completed 3-12-85
Date Plugging Commenced 3-1-96
Date Plugging Completed 3-6-96

The plugging proposal was approved on 3-5-1996 (date)
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?
Producing Formation(s) _____ Depth to Top _____ Bottom _____ T.D. 3930

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	212'	8 5/8	212'	0
	3-18-96	0	3900	5 1/2	3900	1530ft.

RECEIVED
KANSAS CORP COM
1996 MAR 18 10 51 AM

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped sand to 3237' plus 5sx. cement on top of sand.
Shot off casing at 1530' and pulled. Allied pumped 300# hulls - 10 gel -
50 cement - 10 gel - 100# hulls - 8 5/8 plus - 100 cement - 60-40 poz. 6% gel.
Mat pressure 500# SIP 50#. 50' down to cement - filled with sand +
2sx. cement. (If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Pratt Well Service Inc.
License No. 5893
Address Box 847 Pratt, ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pratt Well Service Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Julia Berry (Employee of Operator or Operator) of above-described well, being first

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Julia Berry
(Address) Go PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 96
Dorothy M. Furgason
Notary Public
My Commission Expires: 02/06/97