

15-195-00919-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 2 Twp. 23 Rge. 13 XXXXX (W)

Location as "NE/CNWxSWx" or footage from lines NW NW NW

Lease Owner D.R. Lauck Oil Company, Inc & Sunray Mid-Continent

Lease Name Mawhirter Well No. 1

Office Address Wichita Kans

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 18 19 56

Application for plugging filed May 18 19 56

Application for plugging approved May 18 19 56

Plugging commenced May 18 19 56

Plugging completed May 18 19 56

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation Depth to top Bottom Total Depth of Well 3840 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	232'	8 5/8"	232'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud;
90 sacks cement with 4% calcium
chloride pumped on top of plug;

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oilwell Cementing Co.
Address Great Bend Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
John H. Knightley (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22 day of May, 19 56

My commission expires Sept. 14, 1959

Elizabeth Gay Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 2 T 23 R 13W
BOOK PAGE 63 LINE 24

MAY 24 1956
CONSERVATION DIVISION
Wichita, Kansas

15-185-00919-0000

D.R.Lauck Oil Company, Inc.
& Sunray Mid-Continent Oil Company

NW NW NW Sec.2-23S-13W
Stafford County Kansas

Mawhirter No.1

Commenced: May 8, 1956
Completed: May 18, 1956

Casing Record: 232' 8 5/8" cem.w/ 200 sacks
Elevation: GR 1863; DF 1866; KB 1868;

Drillers Log

Tops

Sample

Sand	225
shale	232
sandy lime & sand	245
red bed	725
Anhydrite	750
red bed shale & shells	1085
shale & shells	1300
shale & salt	1400
shale & lime shells	1510
lime & shale	2045
lime	2170
lime & shale	2415
shale & shells	2455
shale & lime	2685
shale & shells	2885
lime & shale	3225
lime	3275
shale & lime	3420
lime	3655
lime & shale	3700
lime, shale & chert	3740
chert	3790
shale	3840

Heebner	3264-1396
Brown Lime	3400-1532
Lansing	3415-1547
Base Kansas City	3767-1799
Viola	3724-1856
Simpson shale	3785-1919
Arbuckle	3833-1965
Rotary Total Depth	3840-1972
DST #1	3577-3615; open 1 hr; weak steady blow for 1 hour; Recovered 45' mud; IFP 0#; FFP 0#; BHP 1240# in 20 min;
DST#2	3834-3840 RTD Open 1 hr; weak steady blow 1 hour; recovered 80' muddy sulphur water; IFP 0#; FFP 0#; BHP 1240# in 30 min.

Rotary Total Depth 3840

D & A

PLUGGING
FILE SEC <u>2</u> T <u>23</u> R <u>13W</u>
BOOK PAGE <u>63</u> LINE <u>24</u>