


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 12 Twp. 22 Rge. 12 (E) W. (W)  
Location as "NE/CNW/SW" or footage from lines Gen. SW NE SE  
Lease Owner Cities Service Oil Company  
Lease Name Willinger Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 3, 19 56  
Application for plugging filed April 3, 19 56  
Application for plugging approved April 3, 19 56  
Plugging commenced April 3, 19 56  
Plugging completed April 3, 19 56  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production ----- 19 ---  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation Arbuckle Depth to top 3594 Bottom 3625 Total Depth of Well 3625 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	338'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3625-270', mud.  
270-200', wood plug, hulls and 20 sacks cement.  
200-40', mud.  
40' to base of cellar, wood plug, hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Prime Drilling Company  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
V. M. Conover (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover  
Box 751, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of April, 19 56

My commission expires 3-12-59. W. G. Smith Notary Public.



APR 12 1956  
4-12-56

# WELL RECORD

15.185.11486-0000

Company Cities Service Oil Company Well No. 1 Farm Willingor  
 Location 990' South and 990' West of E/4 Cor. Sec. 12 T. 22 R. 12W  
 Elevation 1789 (1786 Cr.) County Stafford State Kansas  
 Drlg. Comm. March 22, 1956 Contractor Prime Drilling Company  
 Drlg. Comp. April 3, 1956 Acid None  
 T. D. 3625' Initial Prod. Dry Hole - P. & A. 4-4-56

CASING RECORD:

8-5/8" O 339' cement 225 net cement

FORMATION RECORD:

surface sand & clay	0-10
clay	78
shale & shells	100
red bed & shells	339
red bed & shale	590
shale & shells	790
anhydrite	915
shale & lime	1155
shale & shells	1405
lime & shale	2510
shale & lime	2675
lime	2720
shale & lime	2770
lime	3105
lime & shale	3200
lime	3625 T. D.

Rechner	3072'
Brown Limestone	3202'
Lansing	3227'
Vicia	3497'
Simpson	3552'
Arbuckle	3594'
Penetration	31'
Total Depth	3625'

Drill stem test 3595-3600, open 1 hr., recovered 30' slightly gas-cut mud; D. H. P. 150#/1 hr.

SLIP TESTS (SURE SHOT):

500'	3/4"
1000'	1/2"
1500'	1/2"
2000'	1/2"
2500'	3/8"
3000'	1/8"
3300'	1"

**PLUGGING**

WELL SEC 12 T 22 R 12W

BOOK PAGE 51 LINE 23