


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 12 Twp. 22 Rge. 12 (E) W (W)

T - 22 NORTH R - 12W



Locate well correctly on above Section Plat

Location as "NE/CNWxSWx" or footage from lines NW NW NW
Lease Owner Frank J. Black
Lease Name Kreie Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-15-53 19
Application for plugging filed 12-20-61 19
Application for plugging approved 12-26-61 19
Plugging commenced 12-22-61 19
Plugging completed 1-4-62 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3628 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	263'	None
				5-1/2"	3626'	2520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3628', sanded to & 3615' and dumped 5 sacks of cement @ 3615' with dump bailer. Pulled 5 1/2" casing. Checked fluid, bailed fluid to 180', set 10' rock bridge to 170' and ran 20 sacks of cement @ 170'. Mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

1-11-62

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1962
CONSERVATION DIVISION
Wichita

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 62

My commission expires May 20, 1964 Milton J. Volin Notary Public.

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- BUICK DRILLING, INC.
Farm- Kreie No. 1

SEC. 12 T. 22 R. 12W
NW NW NW

Total Depth. 3626
Comm. 8-1-53 Comp. 8-15-53
Shot or Treated.
Contractor. Buick Drilling, Inc.
Issued. 10-24-53

County Stafford
KANSAS



CASING:

8 5/8" 263'

Elevation. 1837 DF

Production. 7 BO & NW

Figures indicate Bottom of Formations.

sub-soil, clay & sand	100
clay, shale, shells & red bed	220
shale & red bed	440
red bed	600
anhydrite	625
shale & shells	1650
lime & shale	2440
shale, lime, & shells	2610
lime & shale	2915
lime	2965
sandy shale	3011
lime	3095
lime & shale	3325
lime	3565
chert	3581
lime & shale	3617
lime	3626
Total Depth	

Shot Tops:	
Brown Lime	3243
Lansing	3278
Base-Kansas City	3504
Viola	3540
Simpson	3575
Arbuckle	3617

REIVED
CONSERVATION COMMISSION

DEC 22 1961
12-22-61
CONSERVATION DIVISION
Wichita, Kansas

24-22-18W
G. Blackwell 2
D17210
2/8/17
15.145-20 293 (106)
20277