


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County, Sec. 12 Twp. 22S Rge. 12 (W)
Location as "NE/CNW/SW" or footage from lines NE Corner of NW/4
Lease Owner Graham-Michaelis Drilling, Inc.
Lease Name Wokaty Well No. 1
Office Address 211 North Broadway, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed June 7, 19 49
Application for plugging filed September 10, 19 70
Application for plugging approved September 11, 19 70
Plugging commenced September 25, 19 70
Plugging completed September 29, 19 70
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production August 19 70
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein, Attica, Kansas 67009
Producing formation Arbuckle Depth to top 3572 Bottom 3574 Total Depth of Well 3574 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Sand & Shale			8 5/8"	230'	none
Arbuckle	Lime Chert	3520	3574'	5 1/2"	3572 1/2'	2552'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement plug with 5 sacks cement bottom to 3525', 100 sacks cement, 2 sacks hulls, 15 sacks jell squeezed into Dakota Formation, cement plug to top.

1-11-71
RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Company, Inc. Box 364
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.
211 North Broadway, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 71



Muriel F. C. Jeram
Muriel F. C. Jeram
Notary Public.

My commission expires July 25, 1972

NOTARY WILL NO. 1

Location: NEc NW/4 12-22-12W Stafford County Commenced: 5-27-49
 Operator: Shawver-Graham, Inc. 304 North Market Wichita, Kansas Completed: 6-7-49
 Casing Record: 230' 8 5/8" Surface Cemented with 175 Sacks Regular 3572 1/2' 5 1/2" casing Cemented with 50 Sacks

STATE OF KANSAS COMMISSION
 SEP 14 1970
 CONSERVATION DIVISION
 Wichita, Kansas

LOG

(Figures indicate bottom of formation)

Sand & Shale	230	<u>TOPS</u>	
Red Bed	850	Brown Lansing	3226
Shale & Shells	1110	White Lansing-K.C.	3244
Shale & Lime	1650	Viola Chert	3520
Lime	1865	Simpson Chale	3512
Broken Lime	1810	Arbuckle	3570
Lime & Shale	1915		
Shale & Lime	2910		
Lime	2960		
Shale & Lime	3020		
Lime	3080		
Shale & Lime	3165		
Shale	3265		
Lime	3465		
Lime Chert	3570		
Sand, Lime & Shale	3574		
T.D.	3574		

The undersigned, Shawver-Graham, Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHAWVER-GRAHAM, INC.
 By: [Signature]
 Secretary

STATE OF KANSAS)
) SS
 COUNTY OF SENECA)

BEFORE ME AND THE UNDERSIGNED, a Notary Public, duly commissioned in and for the county of Seneca, Kansas, came WILLIAM L. OGDEN, Secretary of the Shawver-Graham, Inc., a Corporation, personally known to me to be such officer, and to be the said person who executed as such officer, the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

[Signature]
 Notary Public