

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County, Sec. 6 Twp. 22 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner WESTERN PETROLEUM CO., INC.

Lease Name TIEPERMAN Well No. 1

Office Address 925 PATTON ROAD, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed AUGUST 5, 1962 19

Application for plugging filed AUGUST 5 1962

Application for plugging approved AUGUST 5 1962


Plugging commenced AUGUST 5 1962

Plugging completed AUGUST 6 1962

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. LA KAMP

Producing formation Depth to top Bottom Total Depth of Well 3705 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			263	8-5/8"	7/28/62	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE TO 200' WITH ROTARY MUD. PUSHED WOODEN PLUG AND HULLS TO FLUID WITH DRILL PIPE. CEMENTED WITH 20 SXS. CEMENT THROUGH DRILL PIPE. FILLED HOLE TO 35'. PUSHED PLUG AND HULLS TO FLUID. CEMENTED WITH 10 SXS. CEMENT. JOB COMPLETED @ 1:00 AM 8/6/62.

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1962
CONSERVATION DIVISION
Wichita, Kansas

8-8-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS COUNTY OF BARTON, ss.

F. L. COPELAND (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. L. Copeland

925 PATTON ROAD, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 6th day of AUGUST, 1962

Reva C. Brown Notary Public.

My commission expires JANUARY 15, 1963

DRILLERS LOG

#1 Tiepermann

COMPANY:	Western Petroleum Co., Inc.	DESCRIPTION:
CONTRACTOR:	Western Petroleum Co., Inc.	NE NE SE Section 6-T22S-R12W Stafford County, Kansas
COMMENCED:	July 28, 1962	
COMPLETED:	August 5, 1962	ELEVATION:
CASING RECORD:	257.05' 8-5/8" 20# Pipe	1876 DF 1878 KB

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1962
CONSERVATION DIVISION

TOTAL DEPTH: 3705'

FORMATION	FROM	TO	REMARKS
Sand & Clay	0	40	Spudded 9:00 AM 7/28/62. Ran 8-5/8" 20# pipe (257.05), set @ 263' cemented w/235 sx sunset cement. Plug down @ 2:00 PM.
Sand & Shale	40	200	
Red Bed	200	680	DST #1 3676-81. Open 1 hour. Weak blow 34". Recovered 60' watery mud w/few oil specks. IBHP 890#/30", FBHP 185#/30". IFP 0#; FFP 30#. HH 1975#. D&A 8/5/62
Anhydrite	680	705	
Shale & Shells	705	1495	
Lime & Shale	1495	1650	
Lime	1650	1818	
Lime & Shale	1818	2042	
Shale & Lime	2042	2925	
Lime & Shale	2925	3005	
Bn. Lime	3005	3125	
Lime & Shale	3125	3185	
Shale & Lime	3185	3320	
Lime	3320	3560	
Lime & Chert	3560	3615	
Shale & Lime	3615	3677	
Lime	3677	3705	
RTD	3705		

ELECTRIC LOG TOPS

Anhydrite	686	-1192
Tarkio	2573	-695
Topeka	2880	-1002
Heebner	3172	-1294
Iatan	3304	-1426
Lansing	3322	-1444
Base Kansas City	3531	-1653
Viola	3573	-1695
Simpson	3616	-1738
Arbuckle	3676	-1798

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

WESTERN PETROLEUM CO., INC.

F. L. Copeland
F. L. Copeland, Drilling Supt.

Subscribed and sworn to before me this 13th day of August, 1962.

My Commission Expires 1/15/63.

Reva C. Brown
Reva C. Brown, Notary Public