


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 6 Twp. 22 Rge. 12 (~~S~~) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines... SW SE SE
Lease Owner... Iron Drilling Company
Lease Name... Tieperman Well No. 1-A
Office Address... 1206 Philtower Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed... 5/26/48 19
Application for plugging filed... 5/26/48 19
Application for plugging approved... 5/26/48 19
Plugging commenced... 5/26/48 19
Plugging completed... 5/26/48 19
Reason for abandonment of well or producing formation... Dry

If a producing well is abandoned, date of last production... 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?... Yes

Name of Conservation Agent who supervised plugging of this well... C. D. Stough
Producing formation... Depth to top... Bottom... Total Depth of Well 3727 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	255	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

Heavy Mud Circulated from Top to Bottom
Wood Plug Set 250 feet & dumped 15 sax Cement
" " " 25 " " 10 sax Cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to... Iron Drilling Company
Address... 1206 Philtower Bldg.
Tulsa, Oklahoma


STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Herrick Babcock (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) Herrick Babcock Partner
1206 Philtower Bldg., Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of June, 19 48

My commission expires

FILE SEC 6 TYP 172
PLUGGING
BOOK PAGE 33 LINE 16



DRILLING RECORD

15.185-19415-0000

Well No. 1-A Tieperman
 SW SE of Sec 6-22-12W
 Stafford County, Kansas

Casing Record

255' of 8-5/8" Surface Pipe
 cemented with 150 sax.

No Oil String - Dry Hole

Work Commenced 5/12/48
 Drilling Commenced 5/12/48
 Drilling Completed 5/26/48
 Work Completed 5/27/48

WELL LOG

Surface Sand	0 to 215
Red Rock	215 to 255
Red Bed & Shells	255 to 440
Shale & Shells	440 to 680
Anhydrite	680 to 720
Shale	720 to 825
Shale & Shells	825 to 1160
Salt & Shells	1160 to 1440
Shale & Lime	1440 to 1590
Lime	1590 to 1875
Lime Shale	1875 to 1920
Lime	1920 to 1940
Broken Lime	1940 to 2035
Shale & Shells	2035 to 2160
Lime & Shale	2160 to 2605
Shale & Broken Lime	2605 to 2715
Lime & Shale	2715 to 2855
Shale	2855 to 2880
Lime	2880 to 3415
Lime & Shale	3415 to 3465
Lime	3465 to 3590
Conglomerate	3590 to 3637
Lime	3637 to 3660
Lime & Shale	3660 to 3680
Cherty Shale	3680 to 3695
Lime	3695 to 3727
Arbuckle	3711 to 3727

TD Plugged & Abandoned 5/26/48

JUN 11 1948

PLUGGING
 FILE SEC 6 T 22 R 12 W
 BOOK PAGE 33 LINE 16