

51


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Stafford County, Sec. 6 Twp. 22 Rge. 12 (E) (W)
Location as "NE/CNW&SW" or footage from lines NW NW SE
Lease Owner Circle Oil Company, Inc.
Lease Name Tieperman B Well No. 2-1
Office Address 500 Bitting Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4-18-67 19
Plugging completed 5-18-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 3127 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	315	None
				5 1/2	None	2825
RECEIVED STATE CORPORATION COMMISSION MAY 29 1967 CONSERVATION DIVISION				3-29-67		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar. Rigged up unit. Working pipe.

Working pipe. Sanded to 3300'. Dumped 5 sacks of cement. Shot pipe at 2810'. Circulating. Spotted 60 hbl of oil.

Working pipe. Pulling pipe.

Bailing water. Pushed plug to 390' rock bridge. Dumped 10 sacks of cement.

Bailed hole dry. Dumped 15 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25 day of May, 19 67

My commission expires May 27, 1969

Notary Public.

DRILLERS LOGTIEPERMAN "B" NO. 1

CASING RECORD:	COMPANY: Circle Oil Company	DESCRIPTION:
8-5/8" @ 269' w/240 'sax Cement	CONTRACTOR: Sage Drilling Co.	NW NW SE Sec. 6-22S-12W Stafford County, Kansas
TOTAL DEPTH: 3693'	COMMENCED: March 14, 1967	ELEVATION: 1874KB
	COMPLETED: March 22, 1967	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	35	
Sand	35	210	
Shale	210	270	
Red Bed	270	678	
Anhydrite	678	701	
Shale w/Lime Streaks	701	1140	
Lime	1140	1545	
Lime & Shale	1545	2166	
Shale & Lime	2166	2924	
Lime & Shale	2924	3693	

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1967

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By

Thomas M. McCaul, Jr.
Thomas M. McCaul, Jr.

Subscribed and sworn to before me this 24th day of March, 1967.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.