


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 6 Twp. 22 Rge. (E) 12 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NE  
Lease Owner Westgate-Greenland Oil Company  
Lease Name Blackburn Well No. 1  
Office Address 1022 Union National Bank Building  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed April 29, 1949 19  
Application for plugging filed May 2, 1949 19  
Application for plugging approved May 3, 1949 19  
Plugging commenced June 6, 1949 19  
Plugging completed June 9, 1949 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ~~Goodrich~~ Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	300	8 5/8"	300	none
Arbuckle		0	3677	5 1/2"	3677	2986'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 6 sacks cement at 3677' and filled hole with heavy mud to 295' and run 19 sacks cement. Filled with heavy mud to 20' and run 5 sacks cement to cellar base.

(Bridged solid with rock from 300 to 295' then run cement)

RECEIVED

JUN 16 1949

6-16-49

STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company, Attn: G. E. Bitler  
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

G. E. Bitler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) G. E. Bitler

1022 Union National Bank Building, Wichita, Ks  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of June, 1949.

Esther Russell  
Notary Public.

My commission expires May 25, 1953



COMPANY: Westgate Greenland Oil Company  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: Blackburn #1  
 LOCATION: SW SE NE Section 6-22S-12W  
 Stafford County, Kansas  
 ELEVATION: 1872  
 COMMENCED: April 9, 1949  
 COMPLETED: April 23, 1949 - Rotary  
 April 29, 1949 - Cardwell

0	to	170	Sand & shale
170	to	315	Shale & shells
315	to	790	Red bed & shale
790	to	1250	Shale shells & red bed
1250	to	1535	Red bed & shale salt
1535	to	1780	Lime & shale
1780	to	1995	Lime
1995	to	2505	Shale & lime
2505	to	2620	Shale & shells
2620	to	2825	Lime & shale
2825	to	2895	Shale
2895	to	3095	Lime & shale
3095	to	3115	Shale & shells
3115	to	3205	Lime
3205	to	3328	Shale & lime
3328	to	3355	Lime
3355	to	3450	Lime & shale
3450	to	3621	Lime
3621	to	3659	Lime & shale
3659	to	3692	Lime
		3692	T.D. Rotary
		3713	T.D. Cardwell

8 5/8" casing set at 300 ft. Cemented with 200 sacks cement.  
 5 1/2" casing set at 3677 ft. Cemented with 75 sacks cement.

1000 gallons Dowell service

Dry

Measurements taken from top of derrick floor

JUN 16 1949  
 STATE CORPORATION  
 COMMISSION  
 KANSAS

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Blackburn #1, Section 6-22S-12W, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.

*Clare A. Stewart*  
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 17th day of May, 1949.

*Dorothy J. Wilson*  
 Dorothy J. Wilson

My Commission expires November 30, 1950

