


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 8 Twp. 22 Rge. (E) 1(W)
Location as "NE/CNW*SW*" or footage from lines SW NE SE
Lease Owner PETROLEUM, INC.,
Lease Name UNRUH Well No. 1
Office Address ROUTE #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed FEBRUARY 14 19 53
Application for plugging filed JULY 31 19 64
Application for plugging approved AUGUST 3 19 64
Plugging commenced AUGUST 4 19 64
Plugging completed AUGUST 10 19 64
Reason for abandonment of well or producing formation DEPLETION OF PRODUCABLE ZONES
If a producing well is abandoned, date of last production MAY 9 19 64
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top 3599' Bottom 3603' Total Depth of Well 3914' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	223'	NONE
				5-1/2"	3914'	2822'
KC-L	WATER & SMALL AMOUNT OF OIL	3468	3695			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

SANDED OFF BOTTOM TO 3580, MIXED AND RAN 5 SACKS CEMENT WITH DUMP BAILER. MUDDED UP WITH HEAVY MUD TO 223' FOLLOWED BY 10 SACKS GEL. AND 75 SACKS CEMENT. CAPPED WELL WITH 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1964

8-25-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SOUTHWEST CASING PULLING, INC.,
Address BOX 364, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner/representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
ROUTE #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 19TH day of AUGUST 19 64

My commission expires SEPTEMBER 23, 1967

Edward C. Givins
Notary Public.