

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record  
K.A.R. -82-3-117

API NUMBER 15-185-215800001  
LEASE NAME Ahnert "OWWO"  
WELL NUMBER #1

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

2410 Ft. from North Line of Section  
990 Ft. from East Line of Section

LEASE OPERATOR Rupe Oil Company, Inc. SPOT LOCATION 100' South of Sw Se Ne  
ADDRESS P.O. Box 783010 Section 10 Township 22s Range 12w  
CITY, STATE, ZIP Wichita, Kansas 67278 County Stafford  
PHONE # 316-262-3748 Date Well Completed August 26, 1998  
Character of Well Dry and Abandoned Date Plugging Commenced August 26, 1998  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 26, 1998

The plugging proposal was approved on August 24, 1998 at 10:00 am (date)  
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 1029

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	200	and		
Redbeds	Shale	200	310	8-5/8"	290' existing in hole	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Heavy mud from 1029' to 600' then 50 sacks, then heavy mud to 310' then 50 sacks,  
then heavy mud to 40' then 10 sacks. 10 sacks in the rathole and 15 sacks in the  
mousehole. Used 60/40 Poz, 6% Gel for plugging. Started plugging well at 11:45 pm  
on 08-26-98. Plug down at 2:00 am on 08-26-98 by Allied. Ticket # 2510.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rupe Oil Company, Inc. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

10-1-98

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]  
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 25th day of Sept. 19 98

[Signature]

(Notary Public)



My Commission Expires:

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (316) 672-9508, Fax 672-9509

## SAMPLE LOG

Ahnert "OWWO" #1

**LOCATION:** 100' South of Sw Se Ne Section 10 T 22s R 12w  
**API:** 15-185-215800001 Stafford County, Kansas

**OWNER:** Rupe Oil Company, Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 25-Aug-98  
**COMPLETED:** 26-Aug-98

**TOTAL DEPTH:** **DRILLER**

1029
------

 FEET  
**LOGGER**

Not logged
------------

 FEET

**Ground Elevation:** 1846  
**KB Elevation:** 1855

## LOG

0 -	40 FEET	Cement
40 -	180 FEET	Open Hole
180 -	225 FEET	Cement stringers
225 -	310 FEET	Cement
310 -	1029 FEET	Redbeds to RTD

## CASING RECORDS

290' of 8-5/8" surface casing in place.

### Plugged well as follows:

Heavy mud from 1029' to 600' then 50 sacks, then heavy mud to 310' then 50 sacks, then heavy mud to 40' then 10 sacks. 10 sacks in the rathole and 15 sacks in the mousehole. Used 60/40 Poz, 6% Gel for plugging. Started plugging well at 11:45 pm on 08-26-98. Plug down at 2:00 am on 08-26-98 by Allied. Ticket # 2510.

## DEVIATION SURVEYS

None Taken