

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 10 Twp. 22 Rge. 12 E/W
Location as "NE/CNW/SW" or footage from lines
100' South of SW SE NE

Lease Owner L. D. Davis
Lease Name Ahnert Well No. 1

Office Address R. R. 1 Box 183 B
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed April 9 1982
Application for plugging filed April 9 1982
Application for plugging approved April 9 1982
Plugging commenced 9:30 A.M. April 9 1982
Plugging completed 10:30 A.M. April 9 1982
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Metz Stafford, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

600' W/60 sx. cement
270' W/40 sx. cement
40' W/10 sx. cement
10 sx. in rat hole

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1982

CONSERVATION DIVISION
Wichita Kansas

4-20-82

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. D. Drilling

STATE OF Kansas COUNTY OF Barton, ss.
Don Popp (employee of owner) or (~~owner or operator~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Don Popp Hoisington, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 15 th day of April, 19 82

Bessie M. DeWerff Notary Public.

My commission expires 5-20-85



DRILLERS WELL LOG

L. D. DRILLING, INC. - Contractor

L. D. DAVIS - Operator

AHNERT #1
 100' S. SW SE NE
 SEC. 10-22-12
 Stafford County, Kansas

T.D. 3640'
 Elevation 1851' K.B.

Commenced: 4-02-82
 Completed: 4-09-82

CASING:

8 5/8 Set at 290'

CEMENT:

W/300 SX 50/50 Poz 2% Gel 3% CC

FORMATION:

Sand
 Red Bed
 Anhy
 Shale W/Shells
 Shale
 Lime & Shale
 RTD

DEPTH:

0 - 165
 165 - 644
 644 - 671
 671 - 1115
 1115 - 1410
 1410 - 3640
 3640

FORMATION TOPS:

Anhy	684-681
Heebner	3129
Toronto	3147
Douglas	3162
Brown Lime	3260
Lansing	3284
Base K/C	3502
Simpson	3577
Arbuckle	3635
RTD	3640

RECEIVED
 STATE CORPORATION COMMISSION
 APR 20 1982
 CONSERVATION DIVISION
 WASHINGTON

AFFIDAVIT

STATE OF KANSAS)
) SS:
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

Don Popp
 DON POPP

Sworn to and subscribed before me this 19th day of April, 1982.

Bessie M. DeWerff
 BESSIE M. DeWERFF

My Appointment Expires: 5-20-85

