

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 11 Twp. 22 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

NW $\frac{1}{2}$ NE $\frac{1}{2}$ NE $\frac{1}{2}$

Lease Owner Sanders Oil Company

Lease Name Willinger Well No. 2

Office Address 910 Sutton Place, Wichita, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed September 16 19 80

Application for plugging filed September 16 19 80

Application for plugging approved September 16 19 80

Plugging commenced September 16 19 80

Plugging completed September 16 19 80

Reason for abandonment of well or producing formation

D & A


If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owen

Producing formation Depth to top Bottom Total Depth of Well 3660

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

plug @ 450' w/50 sacks cement

240' w/30 sacks cement

Solid bridge @ 40' w/10 sacks

10 sacks in rat hole

2 buckets in water well

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Mustang Drilling, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
Milford Martin (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 1425, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 80



Beverly Shewbart
Notary Public.

10-17-80

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1980
CONSERVATION DIVISION
Wichita, Kansas

My commission expires

DRILLERS' WELL LOG

DATE COMMENCED: September 10, 1980
 DATE COMPLETED: September 16, 1980

Sanders Oil Co.
 "WILLINGER # 2"
 NW NE NE
 Sec 11-T22-R12W
 Stafford County, Kansas

0 - 261' Sand, Shale
 261 - 1330' Red Bed, Shale
 1330 - 1490' Shale
 1490 - 2940' Shale, Lime
 2940 - 3122' Lime, Shale
 3122 - 3126' Shale
 3126 - 3276' Lime, Shale
 3276 - 3509' Lime
 3509 - 3529' Lime, Shale
 3529 - 3569' Lime
 3569 - 3266' Sand, Shale
 3266 - 3660' Dolomite
 3660' RTD

FORMATION TOPS (Log)

Anhydrite 608
 Heebner 3122
 Brown Lime 3251
 Lansing 3276
 Base K.C. 3509
 Vida 3529
 Simpson 3569
 Arbuckle 3266
 RTD 3660

SURFACE PIPE:
 Set used 8 5/8", 28#
 pipe at 255' w/225
 sacks Common, 2% Gel,
 3% cc.

AFFIDAVIT

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

I, Milford Martin of Mustang Drilling, Inc. do state that the above
 is true and correct to the best of my knowledge.

Milford Martin
 Milford Martin

Subscribed and sworn to before me this 22nd day of September, 1980.

BEVERLY SHEWBART
 Barton County, Kansas
 My Commission Expires: April 14, 1982

Beverly Shewbart
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 23 1980
 CONSERVATION DIVISION
 Wichita, Kansas