

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County, Sec. 11 Twp. 22S Rge. (E) 12(W)

Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Circle Oil Company, Inc.  
Lease Name VOIGT "B" Well No. 1  
Office Address 500 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 13, 1967  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced September 13, 1967  
Plugging completed September 13, 1967  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3707 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	221'	8-5/8"	9/7/67	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 200 Feet; Halls, Plug and 25 sacks Cement thru the Drill Pipe; Mud to 40 Feet; 1/2 sack Halls and Plug bridged with Kelly and 10 sacks Cement to Base of Cellar; 2 sacks Cement in Rat Hole. Job completed at 8:30 A.M.

SEP 19 1967  
9-19-67  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sage Drilling Co.  
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray  
500 Bitting Building, Wichita  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 1967

Louise K. Whitted  
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

DRILLERS LOGVOIGT "B" NO. 1

CASING RECORD:	COMPANY:	Circle Oil Company, Inc.	DESCRIPTION:
8-5/8" @ 221' w/200 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	SE SE SW Sec. 11-22S-12W Stafford Co., Kansas
TOTAL DEPTH: 3707'	COMMENCED:	September 7, 1967	ELEVATION: 1857KB
	COMPLETED:	September 13, 1967	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	25	
Sand	25	130	
Shale	130	470	
Red Bed, Shale & Shells	470	1510	
Lime, Shale & Shells	1510	1845	
Lime & Shale	1845	2174	
Shale & Lime	2174	2625	
Lime & Shale	2625	2912	
Shale & Lime	2912	3075	
Lime & Shale	3075	3244	
Shale & Lime	3244	3348	
Lime	3348	3385	
Lime & Shale	3385	3485	
Lime	3485	3598	
Lime, Chert & Shale	3598	3667	
Conglomerate Shale	3667	3707	D & A

RECEIVED  
STATE CORPORATION COMMISSION

SEP 19 1967

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 18th day of September, 1967.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.