


STATE OF KANSAS  
CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 11 Twp. 22 Rge. 12 (E) (W)  
Location as "NE/CNW&SW" or footage from lines SE SW NW  
Lease Owner Morris Sitrin, Inc.  
Lease Name Alexander #2 Well No.  
Office Address Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 12/1/70 19  
Plugging completed 12/1/70 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 3650' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	223'	none
				5 1/2"	3627'	2623'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3650' and ran sand to 3600', dumped 5 sacks of cement. Loaded hole, shot pipe at 3000', 2810', 2715', 2620', worked pipe loose and pulled 82 joints. Allied pumped 3 sacks hulls, 15 mud and 100 cement to plug well.

PLUGGING COMPLETE.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]  
CHASE, KANSAS  
(Address)

Subscribed and Sworn to before me this 8th day of December, 1970

My commission expires 2/15/71

[Handwritten Signature] Notary Public.

DRILLING LOGALEXANDER NO. 2

CASING RECORD:	COMPANY:	Circle Oil Company	DESCRIPTION:
8-5/8" @ 223'	CONTRACTOR:	Sage Drilling Co.	SE SW NW
w/225 sax cement	COMMENCED:	July 6, 1967	Sec. 11-22S-12W
TOTAL DEPTH:	COMPLETED:	July 13, 1967	Stafford County, Kansas
3650			ELEVATION: 1846KS

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	224	
Shale & Red Bed	224	475	
Sand & Shale	475	626	
Anhydrite	626	647	
Shale	647	765	
Shale & Shells	765	1405	
Sandy Lime & Shale	1405	1570	
Lime & Shale	1570	2050	
Shale & Lime	2050	2380	
Lime & Shale	2380	2790	
Shale & Lime	2790	2970	
Lime & Shale	2970	3271	
Shale & Lime	3271	3321	
Lime	3321	3460	
Lime & Shale	3460	3536	
Lime & Chert	3536	3580	
Lime & Shale	3580	3650	5 1/2" @ 3623' w/100 sax

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1970  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 23rd day of October, 1967.