

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,713-0000

LEASE NAME Alexander

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2690 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 11 TWP. 22 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 09-22-90

Plugging Commenced 09-22-90

Plugging Completed 09-22-90

LEASE OPERATOR Globe Exploration, Inc.

ADDRESS P.O. Box 12 Great Bend, KS 67530

PHONE#(316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-21-90 (date)

by Richard Lacey (KCC District Agent's Name),
to be filled

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3682

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 640' w/50 sacks cement thru drill pipe

Next Plug: @ 270' w/40 " " " " " 15 sacks in Rat Hole

Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct so help me God.

(Signature) Leonard Williamson


(Address) P.O. Box 823 Great Bend, KS 67530

SEP 27 1990

SUBSCRIBED AND SWORN TO before me this 25 day of Sept, 1990

CONSERVATION DIVISION
Wichita, Kansas

(Signature) Dorothy M Hague
Notary Public



DRILLER'S WELL LOG

DATE COMMENCED: September 17, 1990
DATE COMPLETED: September 22, 1990

Globe Exploration, Inc.
ALEXANDER #1
280' S of C-S/2 SW NW
Sec. 11, T22S, R12W
Stafford County, Ks.

0 - 128'	Surface Soil, Sand
128 - 624'	Red Bed
624 - 646'	Anhydrite
646 - 1400'	Shale
1400 - 2745'	Lime & Shale
2745 - 3134'	Lime
3134 - 3154'	Shale & Lime
3154 - 3169'	Lime
3169 - 3265'	Shale
3265 - 3281'	Lime & Shale
3281 - 3515'	Lime
3515 - 3573'	Shale, Lime, Chert, Sand
3573 - 3600'	Chert
3600 - 3652'	Sand & Shale
3652 - 3682'	Dolomite
3682'	RTD

Surface Pipe: Set used
8-5/8", 28# pipe @246'
w/160 sacks 60/40pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this _____ day of September 1990.

Dorothy M. Hague
Notary Public

DOROTHY M. HAGUE
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. 5-29-90

RECEIVED
STATE COMMISSION
SEP 27 1990
Wichita, Kansas