

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 11 Twp. 22S Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW

Lease Owner PETROLEUM, INC.

Lease Name Obenhaus Well No. 2

Office Address 100 Derby Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/13 19 49

Application for plugging filed 7/14 19 49

Application for plugging approved 7/14 19 49

Plugging commenced 7/14 19 49

Plugging completed 7/14 19 49

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Ks.

Producing formation Depth to top Bottom Total Depth of Well 3656 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	222'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to surface pipe. Set plug at 224', cemented with 15 sacks cement. Filled hole with mud to 30'. Placed plug at 30'. Filled hole with 10 sacks cement to top of hole.

7-20-49
JUL 20 1949
STATE CORPORATION COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to PETROLEUM, INC.
Address 100 Derby Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Eric H. Jager (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby Bldg., Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of July, 19 49

Ramond Koch
Notary Public.

My commission expires June 7, 1952.

PLUGGING
THE SEC. 11-T-22S-12E
BOOK PAGE 105-11

WELL LOG ODBENHAUS NO. 2

Petroleum, Inc. - Lease Owners

Sec. 11, Twp. 22S, Range 12W

Rotary Total Depth - 3656'

Location: NW NW NW

Commenced: July 3, 1949

County: Stafford County, Kansas

Completed: July 13, 1949

Elevation: 1840' D.F.

Casing: 222' of 8 5/8"

Production:

Figures below indicate bottom of formation.

45	Sand & Surface Clay	3513	Lime
224	Shale & Shells	3560	Lime & Conglomerate
275	Shale, Shells & Red Bed	3587	Conglomerate
640	Red Bed	3596	Viola
665	Anhydrite	3615	Simpson
1100	Shale & Shells	3653	Shale
1490	Salt & Shells	3656	Arbuckle
1525	Shale & Shells		
1980	Lime & Shale	3656	Rotary Total Depth
2180	Shale & Shells		
2300	Broken Lime		
2940	Shale & Lime		
2995	Lime		
3075	Shale & Lime		
3155	Lime		
3165	Shale		
3285	Lime & Shale		
3292	Shale		

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

Eric H. Jager
 Eric H. Jager
 [Signature]

STATE OF KANSAS
 : SS
 SEDGWICK COUNTY

JUL 20 1949

STATE CORPORATION

Subscribed and sworn to before me, a Notary Public in said County and State this 19th day of July, 1949. KANSAS

Rosamund Koch
 Rosamund Koch
 Notary Public

My Commission expires: June 7, 1952.

7/19/49

11-22-120
105-28