

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado State Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,185-22,238-0000

LEASE NAME Alexander

WELL NUMBER #2

2970 Ft. from S Section Line

4630 Ft. from E Section Line

SEC. 11 TWP. 22 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 12-17-88

Plugging Completed 2-1-89

LEASE OPERATOR Pintail Properties

ADDRESS 412 E. Douglas, Suite #1, Wichita, Ks. 67202

PHONE # (316)-264-1144 OPERATORS LICENSE NO. 5086

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 19, 1988 (date)

by Paul Luthi and Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3760'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	344'	None
				6-1/2"	3759'	2,530.40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3300' and 5 sacks cement. Shot casing at 2700' & 1650'. Pulled 80 joints of 5-1/2" casing. B.J. Titan plugged well with 350# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 50# hulls, released plug and pumped 120 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 800 psi and shut in 500 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Properties

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1989

Iona M. Leatherman

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

My Commission Expires: