


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 11 Twp. 22 Rge. 12 (E) W. (W)
Location as "NE/CNW/SW" or footage from lines 330' N. & 990' E. of Center
Lease Owner Cities Service Oil Company
Lease Name Voigt Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed March 13, 19 50
Application for plugging filed June 5, 19 53
Application for plugging approved June 9, 19 53
Plugging commenced June 19, 19 53
Plugging completed June 25, 19 53
Reason for abandonment of well or producing formation Depleted formation.

If a producing well is abandoned, date of last production June 8, 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 3626 Bottom 3634 Total Depth of Well 3634 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	259'	None
				5-1/2"	3627'	2667'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3634-3600' sand.
3600-3560' 5 sacks cement.
3560-240' heavy mud.
240-180' wood plug, rock bridge and 20 sacks cement.
180-35' mud.
35' to base of cellar, 10 sacks cement.

[Handwritten notes and stamps]
6-30-53

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor G. E. Shull Casing Pulling Company
Address Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 751, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 53

My commission expires March 12, 1955.

W. D. Smith
Notary Public.



WELL RECORD

15-185-12734-0000

Company Cities Service Oil Co. Well No. 1 Farm Voigt
 Location 330' North and 990' East of Center Sec. 11 T. 22 R. 12W
 Elevation 1841 (1839 Gr.) County Stafford State Kansas
 Drlg. Comm. February 26, 1950 Contractor Holm-Louis Drilling Company
 Drlg. Comp. March 13, 1950 Acid 500 gals. 3-14-50; 1000 gals. 3-18-50
 T. D. 3634' Initial Prod. Physical Potential: 143 oil, 63 water, 24 hrs. (3-28-50)

CASING RECORD:

3-5/8" @ 240' cen. 200 sz cement
 5-1/2" @ 3627' cen. 150 sz cement

FORMATION RECORD:

clay	0-75
sand	105
shale & shells	160
sand & shale	252
shale & red bed	615
anhydrite	635
red bed & shale	1410
shale & shells	1700
lime & shale	1830
lime	1895
lime & shale	2170
shale & shells	2345
lime & shale	2655
shale & lime	2785
lime & shale	2950
lime	3105
lime & shale	3225
shale & lime	3290
lime	3353
lime & shale	3360
lime	3556
chert	3572
lime	3629
lime	3629 RTD = 3629 SIM
lime	3634 T. D.

Top Lansing	3273'
Top Cherty Conglomerate	3544'
Top Viola	3552'
Top Simpson Shale	3573'
Top Arbuckle	3626'
Penetration	8'
Total Depth	3634'

8 gals. oil per hr.

SIFO:	500'	10'
	1000'	20'
	1500'	10'
	2000'	10'
	2500'	10'
	3000'	10'

PLUGGING
 PER SEC 11 T 22 R 12W
 BOOK PAGE 106 LINE 38

CONSERVATION DIVISION
 Wichita, Kansas