


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 11 Twp. 22 Rge. 12 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
75' NE NW SE SE

Lease Owner National Crude, Inc.  
Lease Name Voight #1 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 1/5/78 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 1/9/78 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted. \_\_\_\_\_

If a producing well is abandoned, date of last production  
\_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3645  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	254	none
				4 1/2"	3639	2846'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Sanded to 3600' and ran 4 sacks cement. Shot pipe at 2925', 2830', pulled pipe.  
Squeezed hole with 3 sacks hulls, 20 sacks gel, released plug and displaced with  
100 sacks 50/50 pozmix with 2% cc.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of Jan., 19 78

Margaret Melcher  
Notary Public.

My commission expires  
**RECEIVED**  
STATE CORPORATION COMMISSION  
**JAN 18 1978**  
CONSERVATION DIVISION  
Wichita, Kansas



1-18-78

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

NATIONAL CRUDE, INC. - OPERATOR

VOIGHT # 1  
75' NE of NW-SE-SE 11-22-12  
STAFFORD COUNTY, KANSAS

T. D. 3645'  
ELEV. 1849 K B

CASING:

8 5/8" set at 254'  
4 1/2" set at 3639'

CEMENT:

220 sx 50/50 Pozmix, 3% CC  
15 BBL. Salt Flush, 2% Gel,  
150 sx 60/40 Pozmix, salt saturated

COMMENCED: 3 - 7-77

COMPLETED: 3 - 15-77

FORMATION

DEPTH

Sand with Clay Streaks	0 - 145
Shale	145 - 165
Redbed	165 - 625
Anhydrite	625 - 645
Shale & Shells	645 - 1550
Lime & Shale	1550 - 3127
Shale	3127 - 3131
Lime & Shale	3131 - 3635
Dolomite	3635 - 3645

TOPS

Anhy.	625-645
Heebner	3127
Toronto	3144
Doug. Shale	3158
Brn. Lime	3256
Lansing	3280
Viola	3540
Simpson Shale	3586
Arb.	3635


RECEIVED  
STATE CORPORATION COMMISSION  
NOV 23 1977  
CONSERVATION DIVISION  
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS, COUNTY OF BARTON

I, WAYNE DOBBS of the L. D. DRILLING COMPANY

being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.



Wayne Dobbs  
WAYNE DOBBS

Subscribed and sworn to before me on this 16 day of March 1977

My commission expires:



Elsie J. Learned  
Notary Public Elsie J. Learned