

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-185-21,884-0000

LEASE NAME Willinger

WELL NUMBER 1

SPOT LOCATION NW NE NE

SEC. 12 TWP. 22 RGE. 12 (E) OR (W)

COUNTY Stafford

DATE WELL COMPLETED 12-10-83

PLUGGING COMMENCED 12-10-83

PLUGGING COMPLETED 12-10-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Parrish Corporation

ADDRESS 110 N. Market, Suite 201, Wichita, Ks. 67202

PHONE #(316) 263-8726 OPERATORS LICENSE NO. 5228

CHARACTER OF WELL D & A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Stafford, Kansas

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3680'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	359'	

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

40 sx. @ 600', 40 sx. @ 390', 10 sx. @ 40' & Bridge Plug, 15 sx. in Rathole

60/40 Poz-mix, 3% CC, 2% Gel, Plug down @1:00 PM, 12-10-83

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Halliburton LICENSE No. _____

ADDRESS P.O. Box 579, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, SS.

K.T. Woodman (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

12-15-83

(SIGNATURE) K.T. Woodman

(ADDRESS) 1022 Union Center, Wichita, KS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 14th DAY OF December, 19 83

Kathryn A. Voigt
NOTARY PUBLIC

MY COMMISSION EXPIRES April 20, 1985

Kathryn A. Voigt

STATE CORPORATION COMMISSION
RECEIVED
DEC 15 1983
CONSERVATION DIVISION
WICHITA, KANSAS

KATHRYN A. VOIGT
NOTARY PUBLIC
STATE OF KANSAS
Expires 4-20-85

K. T. WOODMAN
 RES. PHONE 733-0418
 OFF. PHONE 265-7650
 WICHITA, KANSAS

D. J. IANNITTI
 PHONE 792-2921
 GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1022 UNION CENTER
 150 N. MAIN
 WICHITA, KANSAS 67202

December 14, 1983

Company:	Parrish Corporation
Farm:	Willinger #1
Location:	NW NE NE
Section:	12-22-12W
County:	Stafford
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3680'
Comm:	December 3, 1983
Comp:	December 10, 1983
Casing:	8-5/8" 24# set @ 359' w/250 sx. 50-50 Common-Poz, 3% CC, 2% Gel

Figures Indicate Bottom Formations:

359	Shale
400	Shale
552	Shale
574	Anhydrite
1035	Shale
1580	Shale & Lime
1840	Shale & Lime
2115	Shale & Lime
2366	Lime & Shale
2585	Lime & Shale
2804	Lime & Shale
2920	Lime & Shale
3071	Lime
3225	Lime & Shale
3297	Lime & Shale
3315	Lime & Shale
3320	Lime
3390	Lime
3446	Lime
3540	Lime
3620	Lime
3680	Lime

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K.T. Woodman
 K.T. Woodman, Partner

STATE CORP. COM. MISSION
 RECEIVED
 DEC 15 1983
 CONSERVATION DIVISION
 Wichita, Kansas