

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG.
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

API NUMBER Drilling Completion 5-23-49 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE.)

LEASE OWNER J.H.Child, Agent

ADDRESS P.O. Box 946 Hutchinson, KS. 67501

LEASE (FARM NAME) Teichmann WELL NO. 4

WELL LOCATION SE SW NW SE SEC. 12 TWP. 22S RGE. 13W (~~EAST~~) (WEST)

COUNTY Stafford TOTAL DEPTH 3678' FIELD NAME Drach

OIL WELL XX GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? Yes.
(IF NOT STATE REASON WHY)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Will notify your representative, Mr. J.H. Metz, Stafford, Kansas.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
J.H.Child, Agent ADDRESS P.O. Box 946 Hutchinson, Ks. 67501

PLUGGING CONTRACTOR Basye Well Servicing Company LICENSE NO. 737

ADDRESS P.O. Box 149 Stafford, Kansas 67578 10-7-81

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO: RECEIVED
STATE CORPORATION COMMISSION

NAME J.H.Child, Agent

ADDRESS P.O. Box 946 Hutchinson, Ks. 67501 OCT 7 1981

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OF ACTING AGENT.

CONSERVATION DIVISION
Wichita Kansas

J.H.Child, Agent

SIGNED: By: J.H.Child
APPLICANT OR ACTING AGENT

DATE: 10/6/81

DAVIS-CHILD:TEICHMANN NO. 4

SE SW NW SE Sec. 12, T 22S, R 13W, Stafford County, Kansas

Elevation: 1887' D.F. (Derrick floor was 3' above ground)

All depths stated below are as of derrick floor.

Total Depth with rotary 3678' D.F. May 23, 1949.

Total Depth with cable tools 3682' D.F. June 2, 1949.

Casing: 8-5/8" - 319' cemented with 200 sacks.
5-1/2" - 3675½' cemented with 100 sacks.Lansing-Kansas City 3338 (-1451)

- 3338-3345 Slightly porous cherty lime with spotted traces of oil stain. Do not recommend testing.
- 3358-3361 Slightly porous fine crystalline lime with spotted traces of oil stain. Do not recommend testing.
- 3420-3422 Slightly porous oolitic lime with spotted traces of oil stain. Do not recommend testing.
- 3458-3462 Partly porous oolitic lime - no oil observed. Do not recommend testing.
- 3496-3499 Slightly porous oolitic lime and fine granular lime with slight spotted trace of oil stain. Probably does not warrant testing.
- 3515-3519 Slightly porous oolitic and fine granular lime with spotted traces of oil stain (zone quite soft). This zone probably warrants testing.

Conglomerate (cherty) 3573 (-1686)Viola (chert) 3580 (-1693)RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1949

CONSERVATION DIVISION
Wichita Kansas

Simpson 3615 (-1728)

3675-3678 Fine crystalline and fine granular dolomite with spotted stains and saturation with "live", brown oil.

It is recommended that this zone warrants testing.

Total Depth with rotary 3678' (-1791) May 23, 1949.

Depths 3678-3682 Drilled with cable tools.

3678-3679 Fine crystalline granular dolomite with small show of oil. At base of dolomite were possibly 2 or 3 inches of pale-green shale.

Arbuckle 3679 (-1792)

3679-3680 Fine-medium crystalline, cherty, oolitic dolomite with considerable fair to good porosity with some good oil saturation and some "free, live" oil.

3680-3682 Fine crystalline fine granular and little "tight" dolomite. Most of cuttings had fine, low porosity with much oil stain and saturation (estimated to comprise 75% of sample), a little shale and shaly dolomite was also present.

Total Depth with cable tools 3682 (-1795) June 2, 1949.

Of the six zones described in the Lansing-Kansas City limestone, four appeared to have no commercial possibilities. The fifth zone is of very questionable character and it is concluded that the sixth zone probably warrants testing in addition to the Simpson zone.

Delmer L. Powers
Delmer L. Powers
June 18, 1963

RECEIVED
STATE CORPORATION COMMISSION

OCT 7

CONSERVATION DIVISION
Wichita Kansas

J. H. CHILD, Agent

P.O. Box 946

HUTCHINSON, KANSAS 67501

October 6, 1981

Kansas State Corporation Commission
200 Colorado-Derby Building
Wichita, Kansas 67201

Att: Ms. Allaweas Winfrey


Dear Ms. Winfrey:

In accordance with our phone conversation this morning, we are enclosing Well Plugging Application.

We hope to be able to plug the well some time later this month after testing a zone in the Kansas City formation. It is our understanding, if after testing, the zone is non-productive, we can notify your representative, Mr. Metz, Stafford county, and he will work with us in the plugging operation.

If, for any reason, this is not correct nor in proper procedure, please let us know.

Very truly yours,


J.H. Child, AgentJHC:jd
Enc. 2RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1981

CONSERVATION DIVISION
Wichita, Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202

October 22, 1981

WELL PLUGGING AUTHORITY

Well No.	4
Lease	Teichmann
Description	SE SW NW SE
Section	12-22S-13W
County	Stafford
Total Depth	3678'
Plugging Contractor	Basye Well Servicing Company

J. H. Child, Agent
P.O. Box 946
Hutchinson, KS., 67501
Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,



DELBERT J. COSTA Administrator

Mr. J. H. Metz, Box 55, Stafford, KS. 67578
is hereby assigned to supervise the plugging of the above named well.