

To: 1 120830
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-27 API NUMBER 15- 185-22,911-0000
100' S of
NW NW SE, SEC. 4, T 23 S, R 13 W
2210 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6141
Operator: Coronado Oil & Gas Inc.
Name:
Address: Box 1285
Great Bend, KS 67530

Lease Name Green "A" Well # 1
County Stafford 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 27 Month: 9 Year: 1993

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3898' w/135 sx cement, PBD 3884', Perfs at 3862-66'

1st plug sand back to 3810' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:30 p.m. Day: 27 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3810' and dumped 5 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
10-6-93 OCT 06 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.

INVOICED

(Additional description is necessary, use BACK of this form.)

DATE 10-9-93 I (did / observe this plugging.

INV. NO. 38892

Signed Duane Rankin
(TECHNICIAN)