

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW SE SW , Sec. 4 , T 23 S, R 12 W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185 - 21,921 - 0000

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6462

Lease Name Scheib Well # 1-896-1

Operator: Kennedy & Mitchell, Inc.  
Name & Box 27D, 3190 S. Wadsworth  
Address Denver, CO 80227

County Stafford

Well Total Depth 3950 feet 128.37

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DaMac Drilling, Inc. License Number 6333

Address Box 1164, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 22 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Cliff Summers

(company name) Kennedy & Mitchell (phone) 316-792-6522

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 3860' with 50 sx cement

2nd plug at 1430' with 25 sx cement

3rd plug at 400' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rathole with 15 sx cement,

Plug mousehole with 10 sx cement and

waterwell with 5 sx cement.

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:30 pm Day: 22 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3860' with 50 sx cement, 2nd plug at 1430' with 25

sx cement, 3rd plug at 400' with 50 sx cement, 4th & 5th plugs solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement, mousehole with 10 sx cement and waterwell with 5 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. by Sun Oil Cementing.

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed [Signature] ✓  
(TECHNICIAN)

INVOICED  
DATE 2-1-84  
INV. NO. 9305 W  
1-22

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1984  
CONSERVATION DIVISION  
Wichita, Kansas