

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02089-00-00
Spot: CSESWNE Sec/Twnshp/Rge: 30-22S-11W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: KOMAREK V Well Number: 15
County: STAFFORD Total Vertical Depth: 3586 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: PO BOX 780
MIDDLEBURG, VA 20118

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 13 feet: 220 WITH 225 SX CMT
Production: Size 6 feet: 3580 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2001 9:00 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: BENNIE GRIFFIN Company: LAVETA OIL & GAS Phone: (540) 687-8219

Proposed Plugging Method: SAND TO 3120' & 6 SX CMT. 1ST PLUG AT 610' WITH 20 SX GEL - 90 SX CMT. TAG CMT WITH TUBING AT 550'. RUN TUBING TO 250 PUMP 50 HULLS & 10 SX GEL - 90 SX CMT. PULL TUBING TO 30' & PUMP 60 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/14/2001 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3580-3586'. SANDED TO 3120' & 6 SX CMT ON TOP OF SAND WITH DUMP BAILER. PUMPED PLUG THROUGH CASING. DISPLACED 20 SX GEL - 90 SX CMT AT 600'. NO CIRCULATION. 12/12/01: TAGGED CMT WITH TUBING AT 550'. 12/13/01: RAN TUBING TO 250' & PUMPED 50# HULLS & 10 SX GEL - 90 SX CMT. PULLED TUBING TO 30' PUMPED 60 SX CMT. 12/14/01: TOPPED OFF WELL WITH 75 SX CMT. SCOTT ALBERG WITNESSED PLUG ON 12/13/01.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 610' OF 6" CASING.

Plugged through: CSG

District: 01

12-31-01 Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED INVOICE # DEC 27 2001

DEC 31 2001 DATE 01-02-02
NCC WICHITA INV. NO. 2002061111

Form CP-2/3