

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ⁰¹ ~~15-185-02088-00-00~~
Spot: NWSENE Sec/Twnshp/Rge: 30-22S-11W
~~990~~ feet from N Section Line, ~~1650~~ feet from E Section Line
Lease/Unit Name: VIVIAN KOMAREK Well Number: 14
County: STAFFORD Total Vertical Depth: 3545 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: PO BOX 780
MIDDLEBURG, VA 20118

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 13 feet: 220 WITH 225 SX CMT
Production: Size 6 feet: 2523 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2001 4:30 PM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: BENNIE GRIFFIN Company: LAVETA OIL & GAS Phone: (540) 687-8219

Proposed Plugging Method: SAND TO 3193' & 6 SX CMT. PUMP 250 SX CMT DOWN 6".

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 12/11/2001 5:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3314-3439'. OPEN HOLE FROM 3523-3545'. SANDED TO 3193'. DUMPED 6 SX CMT ON TOP OF SAND WITH DUMP BAILER. TOP PART OF HOLE CEMENTED IN BETWEEN 13" & 6". SHOT 6" AT 600'. PUMPED 250 SX CMT DOWN 6". MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 100#.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

DEC 31 2001

INVOICED

DEC 27 2001

12-31-01

WICHITA

DATE 01-02-02

WV. NO. 200206111

Form 

