

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02084-00-00
Spot: CSENESE Sec/Twnshp/Rge: 30-22S-11W
1650 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: KOMAREK V Well Number: 9
County: STAFFORD Total Vertical Depth: 3625 feet

Operator License No.: 31995
Op Name: GRIFFIN, CHARLES
Address: RT 3 BOX 56
STAFFORD, KS 67578

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 13 feet: 217 WITH 225 SX CMT
Production: Size 6 feet: 3523 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/12/2001 9:30 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: BENNIE GRIFFIN Company: LAVETA OIL & GAS Phone:

Proposed Plugging Method: SAND TO 3410' & 6 SX CMT. 1ST PLUG AT 600' WITH 20 SX GEL - 250# HULLS - 90 SX CMT. 2ND PLUG AT 250' WITH 90 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/13/2001 10:00 AM KC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3523-3525'. SANDED TO 3410' & 6 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 600' WITH 20 SX GEL - 250# HULLS - 90 SX CMT. 2ND PLUG AT 250' WITH 90 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT. TOPPED OFF WELL WITH 75 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 623' OF 6" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
12-31-01 DEC 31 2001 INVOICED DEC 27 2001
WICHITA DATE 01-02-02
WF. NO. 2002061111

Form CD 2/3
