

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02075-00-00
Spot: CNENENE Sec/Twnshp/Rge: 30-22S-11W
330 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: KOMAREK V Well Number: 1
County: STAFFORD Total Vertical Depth: 3570 feet

Operator License No.: 31995
Op Name: GRIFFIN, CHARLES
Address: RT 3 BOX 56
STAFFORD, KS 67578

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 10.75 feet: 237 **\$116.03**
Production: Size 7 feet: 3569
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2001 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: BENNY GRIFFIN Company: LAVETA OIL & GAS Phone: _____

Proposed Plugging Method: SAND BACK TO 3355' & 6 SX CMT. CUT OFF 7" CASING AT 623'. RUN 2 7/8" TUBING IN TO 600'. PUMP DOWN 2 7/8" TUBING WITH 20 SX GEL & 225 SX CMT. CIRCULATE CMT UP ANNULUS. TOP OFF WITH 60 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/14/2001 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

OPEN HOLE 3569-3570'. SANDED BACK TO 3355' & PUT 6 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. CUT 7" CASING OFF AT 623'. LAID DOWN 6' X 7" LANDING SUB. RUN 2 7/8" TUBING IN TO 600'. PUMPED DOWN 2 7/8" TUBING WITH 20 SX GEL & 225 SX CMT. CMT CIRCULATED UP 2 7/8"/7" & 7"/10 3/4" ANNULUSES. LAID DOWN 2 7/8" TUBING. TOPPED OUT 7" & 7"/10 3/4" ANNULUS & WELL CELLAR WITH 60 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 6' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

1-8-02
RECEIVED
KANSAS CORPORATION COMMISSION

INVOICE # DEC 26 2001

Form CP-33

JAN 08 2002

DATE

INV. NO.

Jan 9-02
2002061225

CONSERVATION DIVISION