

1 080493

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
NE NE, SEC. 2, T22 S, R12 W/E
4620 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5569

Lease Name Teichmann Well # 1

Operator: Bea Drilling Company

County Stafford 118.40

Name & Address Drawer 268

Well Total Depth 3643 feet

Sterling, KS 67579

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 pm Day: 5 Month: March Year: 1986

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3642' PRTD 3620' Perfs at 3442-46'; 3381-86'; 3288-90'

1st plug sand back to 3230' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 5 Month: March Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3230' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, and 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1695' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986

INV. NO. 13043

3-20-86 CONSERVATION DIVISION
Wichita, Kansas

Signed J. H. [Signature]
(TECHNICIAN)