

To: 1 120603
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Operator: L.D. Drilling Inc.

Name &

Address P.O. Box 183 B, Route 1

Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 10 a.m. Day: 5 Month: 8 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-793-2943

were: 5 1/2" at 3685' w/150 sx cement, PBTD 3668', Perfs at 3533-3600'

1st plug sand over perfs to 3500' with 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3500' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-27-91

INV. NO. 32845

AUG 13 1991

Signed Duan Rarlan
(TECHNICIAN)

8-13-91

8-5
API NUMBER 15- 185-22,330-0000
NE NE NE, SEC. 2, T 22 S, R 12 W/E
4950 feet from S section line
330 feet from E section line
Lease Name Teichmann Well # 1
County Stafford 119.92