

1 010154

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,108-0000

NW SW SW, SEC. 11, T 22 S, R. 12 W/EK
990 feet from ~~N~~ SE Corner of
4950 feet from ~~W~~ SE Corner of
section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name Voight "C" Well # 1

Operator: Globe Exploration, Inc.

County Stafford

Name & Address P. O. Box 12

Well Total Depth 3658 118.89 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Boger Brothers Oil, Inc. License Number 9421

Address 254 W. 2nd, Hoisington, KS 67544

Company to plug at: Hour: 2:00 pm Day: 3 Month: November Year: 19 84

Plugging proposal received from Smith

(company name) Boger Brothers (phone) 316-653-4739

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 720' with 50 sx cement

2nd plug at 341' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 08 1984
11-8-84

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Kenneth Beakey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 pm Day: 3 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 720' with 50 sx cement, 2nd plug at 341' with 50 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(if additional description is necessary, use BACK of this form.)

INVOICED

(if not) observe this plugging.

DATE 11-18-84

Signed Ken Beakey
(TECHNICIAN)

INV. NO. 4786

11-3

Starting Date: 11-1-84 month day year

API Number 15-185-22108 yes

OPERATOR: License # 6170
Name: Globe Exploration, Inc.
Address: P.O. Box 12
City/State/Zip: Great Bend, KS 67530
Contact Person: Wayne Dohls
Phone: (316) 793-3282

NW SW SW Sec 11 Twp 22 S, Rge 12
990 Ft North from Southeast Corner of Section
4950 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9421
Name: Boger Brothers Drilling, Inc.
City/State: Hoisington, KS 67544

Nearest lease or unit boundary line 330 feet
County: Stafford
Lease Name: Voight "C" Well# 1
Domestic well within 330 feet: [] yes [X] no
Municipal well within one mile: [] yes [X] no

Well Drilled For: Well Class: Type Equipment:
[X] Oil [] Swd [] Infield [X] Mud Rotary
[X] Gas [] Inj [X] Pool Ext. [] Air Rotary
[] OWWO [] Expl [] Wildcat [] Cable

Depth to Bottom of fresh water 109 feet
Lowest usable water formation Top Permian
Depth to Bottom of usable water 250 feet
Surface pipe by Alternate: 1 [X] 2 []
Surface pipe to be set 325 feet
Conductor pipe if any required NA feet
Ground surface elevation Unknown feet MSI
This Authorization Expires 4-12-85
Approved By 10-12-84 K

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 3800 feet
Projected Formation at TD Arbuckle
Expected Producing Formations Lansing-KS & Arbuckle

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C. specifications.
10-10-84 Signature of Operator or Agent Wayne Dohls Title President

Form C-1 484

more on 10-29-84 at 325 of 878

RECEIVED
STATE CORPORATION COMMISSION
NOV 08 1984
CONSERVATION DIVISION
Wichita, Kansas