

1 051352

9-22

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,713 -0000  
280' S of C  
S/2 SW NW, SEC. 11, T 22 S, R 12 W

2690 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name Alexander Well # 1

Operator: Globe Exploration, Inc.

County Stafford 119.666

Name & Address P.O. Box 12

Well Total Depth 3682 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 5:30 a.m. Day: 22 Month: 9 Year: 19 90

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 624-646'

1st plug at 640' with 50 sx cement,

2nd plug at 270' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 a.m. Day: 22 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 640' with 50 sx cement,

2nd plug at 270' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-2-90

INV. NO. 29475

SEP 27 1990

Signed Richard W. Lacey (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

9-27-90

FORM CP-2/3 Rev. 01-84

EFFECTIVE DATE: 9-2-90

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas  
NOTICE OF INTENTION TO DRILL  
15-185-22,713-0000

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Expected Spud Date August 30, 1990  
month day year

280'S of East  
C-S/2.SW.NW. Sec 11. Twp 22. S, Rg 12. X West

OPERATOR: License # 6170  
Name: GLOBE EXPLORATION, INC.  
Address: P. O. Box 12  
City/State/Zip: Great Bend, Kansas 67530  
Contact Person: Ralph Stalcup  
Phone: 316/792-7607

2690 feet from South line of Section  
4620 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5929  
Name: DUKE DRILLING CO., INC.

County: Stafford  
Lease Name: Alexander Well #: 1  
Field Name: Heyen

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... X Infield ... X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWMO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X ... no  
Target Formation(s): Arbuckle  
Nearest lease or unit boundary: 660'  
Ground Surface Elevation: Unknown feet HSL  
Domestic well within 330 feet: ... yes X ... no  
Municipal well within one mile: ... yes X ... no  
Depth to bottom of fresh water: 100'  
Depth to bottom of usable water: 220'  
Surface Pipe by Alternate: X 1 ... 2  
Length of Surface Pipe Planned to be set: 240'  
Length of Conductor pipe required: N/A  
Projected Total Depth: 4000'  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
... well ... farm pond X other

If OWMO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes X ... no  
If yes, total depth location: \_\_\_\_\_

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: ... yes X ... no  
If yes, proposed zone: \_\_\_\_\_  
240' Alt. I Req.

Exp. 2/28/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

RECEIVED  
MINING COMMISSION

Pusher Leard Williamson  
SPUD DATE 9-15-90 INIT. C.M.  
LENGTH SURFACE PLANNED 240'

RESERVE PIT STATUS- REMOVE FLUID \_\_\_\_\_ LINED \_\_\_\_\_  
after salt sect. \_\_\_\_\_ bbls. \_\_\_\_\_ when done \_\_\_\_\_ bbls.

RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 5/8 @ 246 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- 624 B- 646 ELEVATION \_\_\_\_\_

TD 2652 FORMATION Arbuckle  
RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_

Arbuckle Plug @ 561 Ft. W/ 40 SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Anhydrite Base @ 640 Ft. W/ 50 SX  
1/2 Base Anhy. @ 2 Ft. W/ \_\_\_\_\_ SX  
1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Bottom Surface @ 270 Ft. W/ 40 SX  
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX

WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
Hauling \_\_\_\_\_

TECHNICIAN R.L. DATE 9-21-90

TYPE OF CEMENT 60/40 6%

STARTING TIME 5:30 (AM/PM) DATE 9-22-90

COMPLETION TIME 7:30 (AM/PM) DATE 9-22-90

CEMENT COMPANY Allied

SEP 27 1990

CONSERVATION DIVISION  
Wichita, Kansas