

1 120217

2-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,238-0000

SW SE NW, SEC. 11, T 22 S, R. 12 W EX

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Alexander Well # 2

Operator: Pintail Properties

County Stafford 122.20

Name & Address 412 East Douglas, Suite 1

Well Total Depth 3760 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 1 Month: 2 Year: 19 89

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3759' PBTD 3727' Perfs at 3351-54'

1st plug sand back to 3300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

2-3-89
5 1989

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
CONSERVATION DIVISION
Wichita, Kansas

Operations Completed: Hour: 1:30 p.m. Day: 1 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing to 3300' and dumped 5 sx cement

on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2530' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-8-89

INV. NO. 23913

2-1

Signed Paul Luthi
(TECHNICIAN)