

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-00459-00-00 *KCC app 10-19-04 Per Dist 1 GPS'd.*
Spot: ~~NWNWSWNWWSSE~~ *2362* ~~2310~~ feet from S Section Line, ~~2461~~ feet from E Section Line
Lease/Unit Name: WILLINGER Well Number: 1
County: STAFFORD Total Vertical Depth: 3611 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: STE 1775 141 W. JACKSON BLVD
CHICAGO, IL 60604

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 208
Production: Size 5.5 feet: 3608
Liner: Size _____ feet:

117.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2000 10:30 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Revd. from: BENNY GRIFFIN Company: LAVETA OIL & GAS Phone: (316) 234-6189

Proposed Plugging Method: SAND TO 3575 & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 660' WITH 50 SX CMT. 2ND PLUG AT 230' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/19/2000 12:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3546-3552'. SANDED TO 3575' AND 5 SX CMT WITH DUMP BAILER. TRIED TO RUN PERFORATING GUN TO 600' BUT COULDN'T GET GUN PAST 480'. PERFORATED AT 480'. PUMPED 75 SX CMT DOWN 5 1/2" CASING. MAXIMUM PRESSURE 500#. SHUT IN WITH 500#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 5 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN WITH 500#.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 26 2000
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES NO CASING RECOVERED.
Attempted to pull CSG appeared to be squeezed.
Plugged through: CSG

District: 01

Signed *Richard M. Lacey*
(TECHNICIAN)

INVOICED
DATE 12/26/00
WELL NO. 2001064186
DEC 22 2000
MP

[Signature]
Form 2/3