

1 120500

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW SW NE, SEC. 12, T 22 S, R 12 W/E

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6988

Lease Name Willinger Well # 1

Operator: Smith Oil Operations

County Stafford 116.67

Name & Address P.O. Box 550

Well Total Depth 3590 feet

Hutchinson, KS 67504-0550

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:10 p.m. Day: 3 Month: 12 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3588', Perfs at 3239-14'

1st plug sand back to 3150' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 3 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3150' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 50 lbs. hulls, and 100 sx cement.

8 5/8" plate w/2" collar welded in top of 8 5/8".

Pumping pressure 0-700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1200 of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed *Deane Rankin* (TECHNICIAN)

DATE 1-7-91

INV. NO. 30375