

1 080335

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,129-0000

TECHNICIAN'S PLUGGING REPORT

S/2 SW SW , SEC. 6 , T 22 S, R 12 W/X  
330' feet from S section line  
4220' feet from E section line

Operator License # 9963

Lease Name Krankenbergl Well # 1

Operator: Crude Recovery Corporation

County Stafford 123.11

Name & Address 555 N. Woodlawn, Bldg. 1, Ste. 207

Well Total Depth 3788 feet

Wichita, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 253 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Dynasty Drilling License Number 4049

Address 555 N. Woodlawn, Building 1, Suite 207, Wichita, KS 67208

Company to plug at: Hour: 9:30 am Day: 4 Month: March Year: 19 85

Plugging proposal received from Larry Hicks

(company name) Dynasty (phone) 316-681-3601

were: hole full of heavy mud. Spot cement through tubing.

1st plug at 3675' with 50 sx cement

2nd plug at 720' with 50 sx cement

3rd plug at 300' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plug water well with 10 sx cement - fill well from bottom to top.  
Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None N

Operations Completed: Hour: 3:30 pm Day: 4 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3675' with 50 sx cement, 2nd plug at 720' with 50

sx cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, and put 10 sx cement in water well

to fill from bottom to top

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 11 1985 3-11-85

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc b  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-12-85

Signed J. H. Metz  
(TECHNICIAN)

INV. NO. 7302  
3-4

APR 9 1985

15-185-22129-0000

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: November 20 84  
month day year

API Number 15- 185-22,129

OPERATOR: License # 9963  
Name CRUDE RECOVERY CORPORATION  
Address 555 N. Woodlawn, Bldg. 1, Ste. 207  
City/State/Zip Wichita, KS 67208  
Contact Person Vern Brungardt  
Phone 681-3601 4049

S/ 2-SW-SW Sec. 6, Twp 22, S, Rge 12.  
330' Ft North from Southeast Corner of Section  
4220' Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330' feet.  
County Stafford  
Lease Name Krankenberg Well# 1

CONTRACTOR: License # Unknown  
Name 555 N Woodlawn, Bldg. 1, Suite 207  
City/State Wichita, KS

Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class:  
 Oil  Swd  Infield  Pool Ext.  
 Gas  Inj  Wildcat  
 OWWO  Expl  Wildcat

Depth to Bottom of fresh water 110 mhc feet  
Lowest usable water formation Top Permian  
Depth to Bottom of usable water 250 feet  
Surface pipe Alternate: 1  2   
Surface pipe to be set 250 feet  
Conductor pipe if any required feet  
Ground surface elevation feet MSL  
This authorization Expires 5-15-85  
Approved By 11-15-84

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 3750 feet  
Projected Formation at TD Arbuckle  
Expected Producing Formations Arbuckle

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 11-15-84 Signature of Operator or Agent Vern Brungardt Title Manager  
set 250' of 8 5/8 on 12/4/84 mhc/KOHE 11/15/84

Form C-1 4/84

RECEIVED  
STATE CORPORATION COMMISSION

MAR 11 1985  
CONSERVATION DIVISION  
Wichita, Kansas