

To: **1121066**
STATE CORPORATION COMMISSION
Wichita State Office Bldg. **8-31** PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER **15- 7/6/59 15-185-13247-0000**
SW SW NE, SEC. **8**, T **22** S, R **14** W/E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # **3911**
Operator: **RAMA Operating Co., Inc.**
Name: **P.O. Box 159**
Address: **Stafford, KS 67578**

Lease Name **Strobel** Well # **1**
County **Stafford** **126.00**
Well Total Depth **3877** feet
Conductor Pipe: Size _____ feet
Surface Casing: Size **8 5/8** feet **250**

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor **Mike's Testing & Salvage, Inc.** License Number **31529**
Address **P.O. Box 209, Chase, KS 67524**

Company to plug at: Hour: **7** a.m. Day: **31** Month: **8** Year: **19 95**

Plugging proposal received from **Richard McIntyre**
(company name) **Mike's Testing & Salvage, Inc.** (phone) **316-938-2943**

Work: **5 1/2"** at **3873'** w/125 sx cement, Perfs at **3603-05, 3644-46, 3660-64'**
1st plug sand back to **3550'** and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by **Duane Rankin**
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: **8** a.m. Day: **31** Month: **8** Year: **19 95**

ACTUAL PLUGGING REPORT 1st plug sanded **5 1/2"** casing back to **3550'** and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into **8 5/8"** surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls, released **8 5/8"** wiper plug and pumped 100 sx cement
Pumping pressure 0-500 psi and shut in 100 psi.

Remarks: **Used 60/40 Pozmix 6% gel by Allied. Recovered 2023' of 5 1/2" casing.**
(If additional description is necessary, use **BACK** of this form.)

INVOLVED
I hereby acknowledge and observe this plugging.

DATE **9-13-95**
WV. NO. **43537**

Signed **Duane Rankin**
(TECHNICIAN)

RECEIVED
CORPORATION COMMISSION
SEP 6 7 1995
9-7-95