

1 031369.

11-6

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-21,740-0000  
C NE NW, SEC. 8, T 22 S, R 14 W/E  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419  
Operator: Bear Petroleum, Inc.  
Name & Address: P.O. Box 438.  
Haysville, KS 67060

Lease Name Standish Well # BI  
County Stafford  
Well Total Depth 3925 127.56 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Gressel Oil Field Service, Inc. License Number 3009  
Address: P.O. Box 607, Burrton, KS 67020

Company to plug at: Hour: Day: 6 Month: 11 Year: 19 95

Plugging proposal received from Eddie Gressel  
(company name) Gressel Oil Field Service, Inc. (phone) 316-463-5161

Work: 5 1/2" at 3896' w/125 sx cement, PBD 3722', Perfs at 3866-76, 3822-26'  
1st plug sand back to 3775' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None  X

Operations Completed: Hour: 10:30 a.m. Day: 6 Month: 11 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 3775' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 250 psi.

STATE CORPORATION COMMISSION  
NOV - 7 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(Agent) did not observe this plugging.

DATE 11-16-95  
INV. NO. 44037  
11-6

Signed Steve Durrant  
(TECHNICIAN)